



**City of Hamilton**  
**HERITAGE PERMIT REVIEW SUB-COMMITTEE**  
**AGENDA**

**Date:** July 15, 2025

**Time:** 5:00 p.m.

**Location:** YouTube Channel Streaming for Virtual Meetings

All electronic meetings can be viewed at:

City's YouTube Channel:

<https://www.youtube.com/user/InsideCityofHamilton>

*Alissa Golden, Email: [Alissa.Golden@hamilton.ca](mailto:Alissa.Golden@hamilton.ca), Phone: ext. 1202*  
*Lisa Christie, E-mail: [Lisa.Christie@hamilton.ca](mailto:Lisa.Christie@hamilton.ca), Phone: ext. 1291*  
*Meg Oldfield, E-mail: [Meg.Oldfield@hamilton.ca](mailto:Meg.Oldfield@hamilton.ca), Phone: ext. 7163*  
*Scott Dickinson, E-mail: [Scott.Dickinson@hamilton.ca](mailto:Scott.Dickinson@hamilton.ca), Phone: ext. 7167*

---

	<b>Pages</b>
<b>1. CALL TO ORDER</b>	
<b>2. CEREMONIAL ACTIVITIES</b>	
<b>3. APPROVAL OF AGENDA</b>	
(Added Items, if applicable, will be noted with *)	
3.1 HPRC Agenda July 15, 2025	5
<b>4. DECLARATIONS OF INTEREST</b>	
<b>5. APPROVAL OF MINUTES OF PREVIOUS MEETING</b>	
5.1 HPRC Minutes - June 17, 2025	7
<b>6. DELEGATIONS</b>	
<b>7. ITEMS FOR INFORMATION</b>	
<b>8. ITEMS FOR CONSIDERATION</b>	

## 9. HERITAGE PERMIT APPLICATIONS

- |     |   |    |
|-----|---|----|
| 9.1 | HP2025-022 - 55 Main Street West, Hamilton (Former Hamilton Carnegie Building, Part IV)   | 13 |
|     | <ul style="list-style-type: none"> <li>• Installation of two single-swing gates at the west marble stairs in the main lobby for security purposes, including:               <ul style="list-style-type: none"> <li>• Drilling three 1/2" holes for anchoring the vertical support and one 2" hole for power input for each gate; and,</li> <li>• The top gate is to be located at the first tread at the top of the stairs and the bottom gate is to be located at the edge of the stair landing.</li> </ul> </li> <li>• Salvage, collection and storage of materials for repairs to the marble stairs if the gates are removed in the future, including:               <ul style="list-style-type: none"> <li>• Collection of marble dust and fragments produced when drilling the 1/2" holes; and,</li> <li>• Collection of marble plugs when drilling the 2" holes.</li> </ul> </li> </ul> |    |
| 9.2 | HP2025-023 - 122 MacNab Street South, Hamilton (MacNab-Charles Heritage Conservation District, Part V)  | 71 |
|     | <ul style="list-style-type: none"> <li>• Restoration of the brick parapet on the south-west corner of the rear wing of the building, including:               <ul style="list-style-type: none"> <li>• Repointing with a 1-1-6 course cream line mortar with pigment to match; and,</li> <li>• Installing true pressed clay bricks (lbstock) to replace missing or damaged bricks, to match the existing bricks.</li> </ul> </li> </ul>   |    |
| 9.3 | HP2025-025 - 47 James Street South, Hamilton (Landed Bank and Loan Company Building, Part IV)   | 79 |
|     | <ul style="list-style-type: none"> <li>• Structural repairs of the existing brick parapet walls supporting the terra cotta parapet and balustrade at the roof level, including:               <ul style="list-style-type: none"> <li>• Repointing of brick at interior face of parapet, below architectural terra cotta;</li> <li>• Rebuilding of brick and replacement with compatible new brick, as required; and,</li> <li>• Removal and reinstatement of two architectural terra cotta units at interior face of parapet.</li> </ul> </li> </ul>  |    |

## 10. MOTIONS

11. NOTICES OF MOTION

12. ADJOURNMENT





## Heritage Permit Review Subcommittee (Hamilton Municipal Heritage Committee)

July 15, 2025  
Virtual Meeting

*Members of the public are advised that individuals and the media may be audibly and/or visually recording this meeting. Please note that, while this meeting is open to the public for observation, any member of the public wishing to provide comment on any of the agenda items are encouraged to contact Cultural Heritage Planning staff or may choose to give a delegation to the Hamilton Municipal Heritage Committee.*

### Cultural Heritage Planning:

*Alissa Golden, E-mail: Alissa.Golden@hamilton.ca, Phone: ext. 1202*

*Lisa Christie, E-mail: Lisa.Christie@hamilton.ca, Phone: ext. 1291*

*Meg Oldfield, E-mail: Meg.Oldfield@hamilton.ca, Phone: ext. 7163*

*Scott Dickinson, E-mail: Scott.Dickinson@hamilton.ca, Phone: ext. 7167*

## AGENDA

### 1. Approval of Agenda

- July 15, 2025

### 2. Declarations of Interest

### 3. Approval of Minutes from Previous Meetings:

- June 17, 2025

### 4. Heritage Permit Applications

#### a) **HP2025-022** – 55 Main Street West, Hamilton (Former Hamilton Carnegie Building, Part IV)

- Installation of two single-swing gates at the west marble stairs in the main lobby for security purposes, including:
  - Drilling three 1/2" holes for anchoring the vertical support and one 2" hole for power input for each gate; and,
  - The top gate is to be located at the first tread at the top of the stairs and the bottom gate is to be located at the edge of the stair landing.
- Salvage, collection and storage of materials for repairs to the marble stairs if the gates are removed in the future, including:

- Collection of marble dust and fragments produced when drilling the 1/2" holes; and,
  - Collection of marble plugs when drilling the 2" holes.
- b) **HP2025-023** – 122 McNab Street South, Hamilton (MacNab-Charles Heritage Conservation District, Part V)
- Restoration of the brick parapet on the south-west corner of the rear wing of the building, including:
    - Repointing with a 1-1-6 course cream line mortar with pigment to match; and,
    - Installing true pressed clay bricks (Ibstock) to replace missing or damaged bricks, to match the existing bricks.
- c) **HP2025-025** – 47 James Street South, Hamilton (Landed Banking and Loan Company Building, Part IV)
- Structural repairs of the existing brick parapet walls supporting the terra cotta parapet and balustrade at the roof level, including:
    - Repointing of brick at interior face of parapet, below architectural terra cotta;
    - Rebuilding of brick and replacement with compatible new brick, as required; and,
    - Removal and reinstatement of two architectural terra cotta units at interior face of parapet.

**Next meeting:** August 19, 2025



## **HERITAGE PERMIT REVIEW SUB-COMMITTEE MINUTES HPRC 25-006**

**5:00 p.m.**

**Tuesday, June 17, 2025**

Webex Virtual Streaming

---

**Present:** Karen Burke (Chair), Graham Carroll (Vice Chair), Andy MacLaren, Katie McGirr, Matthew LaRose, Carol Priamo

**Absent  
With Regrets:** Andrew Douglas, Sandra Iskandar, Steve Wiegand

**Also  
Present:** Ken Coit (Director of Heritage and Urban Design), Lisa Christie (Cultural Heritage Planner), Gabriel Lam (Assistant Cultural Heritage Planner)

---

### **1. CALL TO ORDER**

Committee Chair K. Burke called the meeting to order at 5:00 p.m.

### **2. CEREMONIAL ACTIVITIES**

There were no Ceremonial Activities.

### **3. APPROVAL OF THE AGENDA**

**(McGirr/MacLaren)**

That the Agenda for June 17, 2025, meeting of the Heritage Permit Review Sub-Committee, be approved, as presented.

**CARRIED**

### **4. DECLARATIONS OF INTEREST**

There were no Declarations of Interest.

### **5. APPROVAL OF MINUTES OF PREVIOUS MEETING**

#### **5.1 HPRS Minutes 25-005 (May 20, 2025)**

**(MacLaren/LaRose)**

That the Minutes of May 20, 2025, meeting of the Heritage Permit Review Sub-Committee, be approved, as presented.

**CARRIED**

**6. DELEGATIONS**

There were no Delegations.

**7. ITEMS FOR INFORMATION**

There were no Items for Information.

**8. ITEMS FOR CONSIDERATION**

There were no Items for Consideration.

**9. HERITAGE PERMIT APPLICATIONS**

**9.1 HP2025-018 – 71 Main Street West, Hamilton (Hamilton City Hall, Part IV)**

- Replacement of 12 automatic swing doors and 18 adjacent glass panels on the front entrance of City Hall to match the existing design and proportions of the existing system with new material.

Cynthia Cenerini and Andrew Chiu were present to give an overview of the project and to answer questions from the committee.

**(Priamo/MacLaren)**

- (a) That Heritage Permit 2025-0018 – 71 Main Street West, Hamilton (Hamilton City Hall, Part IV), be received; and
- (b) That the Heritage Permit Review Sub-Committee advises heritage staff that Heritage Permit Application HP2025-018 be consented to, subject to the following conditions:
  - (i) That any minor changes to the plans and elevations following approval shall be submitted, to the satisfaction and approval of the Director of Planning and Chief Planner, prior to submission as part of any application for a Building Permit and / or the commencement of any alterations; and
  - (ii) That implementation / installation of the alteration(s), in accordance with this approval, shall be completed no later than June 30, 2027. If the alteration(s) are not completed by

June 30, 2027, then this approval expires as of that date and no alterations shall be undertaken without a new approval issued by the City of Hamilton.

**CARRIED**

**9.2 HP2025-019 – 24 Griffin Street, Flamborough (Griffin Stone Cottage, Part IV)**

- Replacement of front entry with a new sympathetic wood entry to match the size and dimensions of the existing transom, sidelights and door, including:
  - New 6 paneled solid wood door, new frame, door, hardware and weatherstripping;
  - Removal of current wood storm door and storm sidelights;
  - Addition of a sash on the interior of transom window, original glass to be maintained; and
  - Construction of sidelights that replicate the originals but with insulated glass units (IGU) and an authentic muntin divider.

*Note: This Heritage Permit application is a resubmission of the previously-approved Heritage Permit HP2021-038, which expired February 28, 2024.*

Jim and Fay Mansfield were present to give an overview of the project and to answer questions from the committee.

**(Carroll/McGirr)**

- (a) That Heritage Permit 2025-0019 – 24 Griffin Street, Flamborough (Griffin Stone Cottage, Part IV), be received; and
- (b) That the Heritage Permit Review Sub-Committee advises heritage staff that Heritage Permit Application HP2025-019 be consented to, subject to the following conditions:
  - (iii) That any minor changes to the plans and elevations following approval shall be submitted, to the satisfaction and approval of the Director of Planning and Chief Planner, prior to submission as part of any application for a Building Permit and / or the commencement of any alterations; and
  - (iv) That implementation / installation of the alteration(s), in accordance with this approval, shall be completed no later

than June 30, 2027. If the alteration(s) are not completed by June 30, 2027, then this approval expires as of that date and no alterations shall be undertaken without a new approval issued by the City of Hamilton.

**CARRIED**

**9.3 HP2025-020 – 8 Margaret Street, Flamborough (Reid House, Part IV)**

- Replacement in kind of wood siding on all elevations of home with new wood siding (Maibec); and,
- Replacement in kind of the existing contemporary eavestroughs with similar profile and colour.

Stephen Dorrell was present to give an overview of the application and to respond to questions and advice from the Sub-Committee.

**(MacLaren/McGirr)**

- (a) That Heritage Permit 2025-020 – 8 Margaret Street, Flamborough (Reid House, Part IV), be received; and
- (b) That the Heritage Permit Review Sub-Committee advises heritage staff that Heritage Permit Application HP2025-020 be consented to, subject to the following conditions:
  - (i) That any minor changes to the plans and elevations following approval shall be submitted, to the satisfaction and approval of the Director of Planning and Chief Planner, prior to submission as part of any application for a Building Permit and / or the commencement of any alterations; and
  - (i) That implementation / installation of the alteration(s), in accordance with this approval, shall be completed no later than June 30, 2027. If the alteration(s) are not completed by June 30, 2027, then this approval expires as of that date and no alterations shall be undertaken without a new approval issued by the City of Hamilton.

**CARRIED**

**9.4 HP2025-021 – 290 Fennell Avenue West, Hamilton (Century Manor, Part IV)**

- Demolition of existing Powerhouse and Trades buildings.

*Note: The two structures proposed to be demolished are not identified in the Reasons for Designation for the property. This Heritage Permit is required*

*because the Ontario Heritage Act now requires approval for the demolition or removal of any building or structure on a designated heritage property.*

Glenn Wellings, Kevin Bushell and Jacqueline McDermid were present to give an overview of the application and to respond to questions from the Sub-Committee.

**(MacLaren/McGirr)**

- (a) That Heritage Permit 2025-021 – 290 Fennell Avenue West, Hamilton (Century Manor, Part IV), be received; and
- (b) That the Heritage Permit Review Sub-Committee advises heritage staff that Heritage Permit Application HP2025-021 be consented to, subject to the following conditions:
  - (i) That any minor changes to the plans and elevations following approval shall be submitted, to the satisfaction and approval of the Director of Planning and Chief Planner, prior to submission as part of any application for a Building Permit and / or the commencement of any alterations; and
  - (ii) That implementation / installation of the alteration(s), in accordance with this approval, shall be completed no later than June 30, 2027. If the alteration(s) are not completed by June 30, 2027, then this approval expires as of that date and no alterations shall be undertaken without a new approval issued by the City of Hamilton.

**CARRIED**

**10. MOTIONS**

There were no Motions.

**11. NOTICE OF MOTIONS**

There were no Notice of Motions.

**12. ADJOURNMENT**

There being no further business, the Heritage Permit Review Sub-Committee was adjourned at 6:09 pm.

Respectfully submitted,

Lisa Christie

Karen Burke, Chair

Cultural Heritage Planner

Heritage Permit Review  
Sub-Committee



HERITAGE PERMIT REVIEW SUBCOMMITTEE  
Meeting Date: July 15, 2025

## City of Hamilton - Heritage Permit Application Note Sheet

**Address:** 55 Main Street West, Hamilton (Former Hamilton Carnegie Building, Part IV)  
**Permit Number:** HP2025-022

---

**Owner:** Infrastructure Ontario

**Applicant/Agent:** Ruchir Mehrotra, Project Manager, Colliers Project Leaders

---

### Description of proposed alterations:

- Installation of two single-swing gates at the west marble stairs in the main lobby for security purposes, including:
    - Drilling three 1/2" holes for anchoring the vertical support and one 2" hole for power input for each gate; and,
    - The top gate is to be located at the first tread at the top of the stairs and the bottom gate is to be located at the edge of the stair landing.
  - Salvage, collection and storage of materials for repairs to the marble stairs if the gates are removed in the future, including:
    - Collection of marble dust and fragments produced when drilling the 1/2" holes; and,
    - Collection of marble plugs when drilling the 2" holes.
- 

### Reasons for proposed alterations:

- The single-swing gates are required to restrict public access up these stairs from the Lobby while allowing exiting down through the stairs in the case of an emergency.
  - These penetrations are required in order to provide the necessary security required by the Ministry of the Attorney General (MAG) for the courthouse.
- 

### Documentation submitted with application:

- Heritage Permit application form
- Heritage Impact Assessment, prepared by a+LINK architecture inc., dated April 16, 2025 (See **Appendix "A"**)

HERITAGE PERMIT REVIEW SUBCOMMITTEE  
Meeting Date: July 15, 2025

**Draft Conditions for Consideration:**

- ☐ That confirmation of the salvaged marble materials and their storage location be provided to the City, to the satisfaction and approval of the Director of Planning and Chief Planner;
- ☐ That any minor changes to the plans and elevations following approval shall be submitted, to the satisfaction and approval of the Director of Planning and Chief Planner, prior to submission as part of any application for a Building Permit and / or the commencement of any alterations; and
- ☐ That implementation / installation of the alteration(s), in accordance with this approval, shall be completed no later than July 31, 2027. If the alteration(s) are not completed by July 31, 2027, then this approval expires as of that date and no alterations shall be undertaken without a new approval issued by the City of Hamilton.

## **Excerpt from Reasons for Designation (By-law No. 87-250)**

---

Limestone ashlar was used in the construction, following local building tradition, and the structure was given a prominent site, set back from the street and raised on a grassy bank, with a formal central stairway providing the approach.

Designed in the neo-classical style of architecture, 55 Main Street West displays a forceful composition of classical features, an imposing monumentality and a formal symmetry that are hallmarks of major public buildings of the period. The design displays a stripped or stylized version of classical detailing.

Important to the preservation of the three stone facades are the building's original features, including but not limited to the two-story pilasters, massive corner piers, the entablature with dentilated cornices the projecting front entranceway, the large recessed multiple windows, the decorative stone mouldings and panels, the exterior stairways and doors, the two flanking free-standing stone walls and the parapet wall.

The Carnegie Corporation's stipulation that the space inside the building be kept unobstructed was successfully followed in the Hamilton library. The open, well-lit interior is articulated by rows of free-standing columns 09/01187 that support a gridwork of dentilated ceiling beams. A central two-story atrium with marble balustrade, double staircase and skylight unifies the interior and provides a spacious and elegant entrance lobby that is a valuable architectural resource of the city.

Important to the preservation of the interior are the original architectural features, including but not limited to the open atrium, the marble double staircase, dado and balustrade, the skylight, the composite columns, wall pilasters and piers, the multiple windows with transoms of lavender-coloured glass, and the dentilated ceiling beams.

HERITAGE PERMIT REVIEW SUBCOMMITTEE  
Meeting Date: July 15, 2025

## Photographs

---




Figure 1: Front view of the Hamilton Carnegie Building at 55 Main Street West from Google Street View (June 2024).

HERITAGE PERMIT REVIEW SUBCOMMITTEE  
Meeting Date: July 15, 2025




Figure 2: Main Floor Plan showing the location of the proposed alterations to the interior west marble stairs.




Figure 3: Mock-ups showing proposed locations of the top and bottom swing gates.

HERITAGE PERMIT REVIEW SUBCOMMITTEE  
Meeting Date: July 15, 2025

## Supporting Documents

---

Please see the Heritage Impact Assessment attached as **Appendix “A”** to this Note Sheet



# HERITAGE IMPACT ASSESSMENT

## Proposed Security Upgrades at UFC Courthouse N05805

55 Main Street W  
Hamilton, ON

Prepared for:  
**Colliers Project Leaders**  
485 Pinebush Road, Suite 202  
Cambridge, ON

**a+LiNK Architecture Inc.**  
362 Dufferin Avenue  
London, ON N6B 1Z4  
(519) 649 0220  
[www.alinkarch.ca](http://www.alinkarch.ca)

**Colliers Project# 1102792-274103**  
a+LiNK Project #: 2341  
**Final Report (R03): 2025-04-16**

---

**a+LiNK**  
architecture inc.  
preserve + create + sustain

# TABLE OF CONTENTS

## HERITAGE IMPACT ASSESSMENT

1. INTRODUCTION .....	4
2. STATEMENT OF CULTURAL HERITAGE VALUE.....	6
3. ASSESSMENT OF EXISTING CONDITIONS .....	7
4. DESCRIPTION & PURPOSE OF PROPOSED ACTIVITY.....	12
5. IMPACT ASSESSMENT .....	15
6. CONSIDERED ALTERNATIVES & MITIGATION MEASURES.....	18
7. RECOMMENDATIONS .....	22

## APPENDICES

### APPENDIX A - *References/Bibliography*

### APPENDIX B - *Project Personnel* a+LiNK Architecture CVs

### APPENDIX C - *Property Designation - By-Law No. 87-250* The Corporation of the City of Hamilton September 1, 1987.

### APPENDIX D - *Drawings - Unified Family Courthouse Security Upgrades* by a+LiNK Architecture Inc. February 13, 2025.

### APPENDIX E - *Data Sheet - Cylinder Speed Gate MT310-S* by MAIRS



# 1. INTRODUCTION

## Overview

The proposed interior renovations to the Main Hall public space at the Unified Family Courthouse (No.N05805), formerly The Carnegie Building, are required by the Ministry of the Attorney General (MAG) for the purposes of providing the increased security infrastructure currently required for the courthouse. These alterations will impact the existing heritage marble west stair in the in the Main Hall of the existing Designated building. Due to the heritage status of the building, a+LiNK has prepared a Heritage Impact Assessment (HIA) for the Unified Family Courthouse building in regards to the proposed interior renovations at the Heritage Lobby to review the potential impact of the proposed renovations on the Designated built heritage resource. This report has been prepared by Ed van der Maarel, Partner, Principal Architect and Heritage Consultant (OAA, CAHP) and Alicia Lesniak, Heritage Consultant/Architect (OAA). The report is being submitted as required by Infrastructure Ontario.

The property is owned by the province of Ontario and is identified as a Provincial Heritage Property (PHP). It is subject to Part III.1 of the Ontario Heritage Act and its management and conservation must comply with the Standards & Guidelines for the Conservation of Provincial Heritage Properties. This HIA was prepared in accordance with MTCS' Information Bulletin 3 - Heritage Impact Assessment for Provincial Heritage Properties to meet the requirements of the Standards and Guidelines.

The purpose of the HIA is to analyze the impact of the proposed interior renovations on the heritage value of the property. As the property at 55 Main Street W is municipally designated under Section 29 of the Ontario Heritage Act (By-Law 87-250) and identified by the Ministry of Infrastructure to be of Local Heritage Significance, an evaluation of the potential impact of the proposed security upgrades on the property's interior heritage attributes is necessary in order to comply with the Provincial Standards and Guidelines. The interior renovations proposed in the form of secure access systems in the Heritage Lobby will directly impact the existing Designated built heritage features, as outlined in the designation By-law 87-250, by requiring alterations to the existing marble stairs. This report will both provide background and baseline information on the existing property and built heritage at 55 Main Street W.

## Context

The Unified Family Courthouse, located at 55 Main Street West, at the corner of Main Street W and McNab Street S, is at the heart of downtown Hamilton. The building is a Municipally Designated under Section 29 of the Ontario Heritage Act. Owned by the Province and managed by the Ministry of Infrastructure (MOI), the property is identified as Provincial Heritage Property (PHP). It is subject to Part III.1 of the Ontario Heritage Act and its management and conservation must comply with the Standards & Guidelines for the Conservation of Provincial Heritage Properties.

Formerly known as the The Carnegie (Hamilton Public Library) Building, it was built in 1909-1913 in the 'Neo-Classical' architectural style by philanthropist Andrew Carnegie. It operated as Hamilton's Main Public Library for 67 years (1913-1980) and after remaining vacant for several years, it had been converted into the province's Unified Family Courthouse in 1986 (opening in 1989). The existing heritage building displays a forceful composition of classical features, an imposing monumentality and a formal symmetry that are hallmarks of major public buildings of the period. As a result, it is an important landmark of the city's cultural heritage and is particularly significant as being one of the few historic civic buildings still standing in Hamilton.

# 1. INTRODUCTION

## **Proposed Activity**

The proposed interior renovations are located in the Main Hall off of the existing main entry at Main Street W. The purpose of the security modifications to the Unified Family Courthouse is to provide a secured Single Point of Entry for the entire building, this includes all public and staff. In order to achieve this, a series of security screens are to be installed to restrict access through the space as well as a screening area. In order for the partitions and walls to be secured to the floor, several posts are required to be anchored to the existing marble tile floor. The 12" x 12" Italian Carrera marble tile set in a grid pattern at the Main Hall floor is not original to the building and therefore the assessment of the impacts of the proposed alterations is not required for this area. It is important to note that although the existing marble stairs are identified in the designation by-law, the floors in the Lobby space are not.

As part of the required security measures, single-swing motorized gates are proposed to be located at the top and bottom of the west stair, located off of the Main Hall and near the Main Entry. The swing gates at the stair are to control access, prohibiting people from bypassing the security checkpoint and gaining access to the building. The west stair, as well as the east stair, is considered to be of heritage value as it demonstrates the use of rich materials and quality of craftsmanship both at the wainscoting, stairs and balustrades. The new gates that are to be installed will have the most impact on the existing marble stair treads at the top and bottom of this stair. Being that the double marble staircase is identified in the designation by-law as an important feature at the interior, the impact of these proposed alterations are to be reviewed to ensure the preservation of this heritage resource.

## **Mitigation Measures**

The potential heritage impact of the proposed interior renovations on the Designated built heritage resource has been assessed and the mitigating approaches reviewed. It has been determined that ultimately, the proposed alterations will have some effect on the existing marble stairs. However, these modifications would have only a minor impact relative to the overall character of the heritage lobby. Suggestions for possible mitigation strategies related to potential impacts of the proposed interior renovations are further outlined in Section 8 of this report.

### *Disclaimer:*

*The area of focus for this report includes the history and value of the property located at 55 Main Street W (the location of the proposed interior renovation). At the time of the report, the information that was available on the specific history of this property has been included. A brief summary of the history of the area and some information on the history of the property has also been included in Section 3.0: Assessment of Existing Conditions of this report. This information has been provided to serve as background for the HIA, but also as a baseline from which to evaluate the cultural heritage value of the property at a high level, and assess the potential impact of the proposed development on this property.*

## 2. STATEMENT OF CULTURAL HERITAGE VALUE OR INTEREST

### 2.1 STATEMENT OF CULTURAL VALUE (SCVH)

As one of more than a hundred libraries built in Ontario by philanthropist Andrew Carnegie during the early 20th Century, the Hamilton building is considered to be one of the finest in the province. Having served as the main public library for 67 years, the building is an important landmark of the city's cultural heritage; it is particularly significant as one of the few historic civic buildings still standing in Hamilton.

Designed in the neo-classical style of architecture, 55 Main Street West displays a forceful composition of classical features, an imposing monumentality and a formal symmetry that are hallmarks of major public buildings of the period. The design displays a stripped or stylized version of classical detailing.

The reasons for designation are defined in the City of Hamilton's Heritage By-law #87-250 referencing the architectural significance of the Heritage Building itself as well as the designated features of the building's interiors. The By-Law's Reasons for Designation specific to the interiors of the heritage building are as follows:

*The Carnegie Corporation's stipulation that the space inside the building be kept unobstructed was successfully followed in the Hamilton library. The open, well-lit interior is articulated by rows of free-standing columns that support a gridwork of dentilated ceiling beams. A central two-story atrium with marble balustrade, double staircase and skylight unifies the interior and provides a spacious and elegant entrance lobby that is a valuable architectural resource of the city.*

*Important to the preservation of the interior are the original architectural features, including but not limited to the open atrium, the marble double staircase, dado and balustrade, the skylight, the composite columns, wall pilasters and piers, the multiple windows with transoms of lavender-coloured glass, and the dentilated ceiling beams.*

Only the interior heritage attributes identified as designated heritage attributes that will be impacted by the proposed alterations (ie. the marble stair, central atrium) have been evaluated in this HIA. Refer to **Appendix C - Statement of Cultural Heritage Value** for further information regarding the designation by-law.

### 3. ASSESSMENT OF EXISTING CONDITIONS

#### 3.1 PROPERTY CONTEXT

The Unified Family Courthouse is located in the downtown core of the City of Hamilton, at the corner of Main Street W and MacNab Street S. This property lies on the boarder of the Beasley Established Historic neighborhood, part of the King Street East Cultural Heritage Landscape, which was one of the first neighborhoods in Hamilton. The neighborhood is predominantly mid to high-rise commercial and institutional uses, with some residential uses towards the north. As part of the Downtown commercial core, this area functions as a cultural and economic focal point for the City of Hamilton. Due to the historic nature of this neighborhood, many of the buildings in this area are either designated or registered (See Map 1). Some of the more notable amenities adjacent to this property are City Hall to the west and FirstOntario Concert Hall to the north. The subject property is bounded by a major arterial road to the north (Main Street W) and a minor arterial road to the south (Jackson St W) and east (MacNab Street S).




Image 5.1: Downtown Hamilton Secondary Plan- Cultural Heritage Resources-Appendix B, Aug. 2019.



### 3. ASSESSMENT OF EXISTING CONDITIONS

#### 3.2 PROPERTY DESCRIPTION

The property at 55 Main Street W is municipally designated under Part IV of the Ontario Heritage Act. Formerly known as the Hamilton Public Library Building, it was built in 1913 in the 'Neoclassical' architectural style with funding from American philanthropist Andrew Carnegie. It is one of the oldest public libraries in Ontario.

The 2-storey building is currently used as the province's Unified Family Courts since 1986. Its north facade plays an integral part of Main Street W streetscape. The UFC Courthouse building sits prominently on the corner of the block and is one of the more dominant facades along the streetscape.



Image 3.2: 55 Main Street W, Hamilton, 3D Map, Google Images, March 2022.

The UFC Courthouse's 2-storey gray limestone facade creates a strong and imposing presence along Main Street W and MacNab Street S. The smooth ashlar facade runs up the two storeys where it terminates with a strong horizontal band. This prominent 'base' becomes more pronounced with the middle grand entrance off of Main Street W centered between the tall window bays along the street-facing facade. The deep recessed windows are set in between vertically fluted limestone pilasters. The building massing is of a monumental public scale, reinforcing the urban streetscape of Hamilton's downtown core.



Image 3.3: Image of Main Street W entrance. Source: Google Street View.

### 3. ASSESSMENT OF EXISTING CONDITIONS

#### 3.3 PROPERTY HISTORY

##### ***UFC Courthouse (Hamilton Public Library Building)***

In 1913, the Carnegie Hamilton Public Library (1913-1980) was constructed with a grant of \$100,000 from American philanthropist Andrew Carnegie. Although there were hundreds of libraries built by Andrew Carnegie across Ontario in the early 20th century, the Hamilton building is considered to be of the finest in the province. The Carnegie Building is a significant component in Hamilton's redeveloped Civic Square block, providing an imposing historically significant architectural presence to the complex. It served as the main public library for 67 years, closing in 1980, and it is one of the few historic civic buildings still standing in Hamilton, thus, contributing to the city's cultural heritage. The building was recognized for its heritage value (City of Hamilton by-law 87-250) and received Heritage Designation under Part IV of the Ontario Heritage Act in 1987.



Image 3.4: Historical image of the Hamilton Public Library Building. Source: Digital Archive Ontario, Toronto Public Library.

It was designed in the neoclassical style by local architect A. W. Peene after winning an international competition for the new library, and it is considered to be his best work in the city. The building was constructed with local building tradition, using limestone ashlar. It was given a prominent site, set back from the street and raised on a green hill, with a main entrance stairway in the center to enter the building. The imposing monumentality and formal symmetry were common in major public buildings of the period.

Its remarkable architectural features at the exterior include two-storey pilasters, massive corner piers, the entablature with a dentilled cornice on the projecting front entrance, and a prominent stairway. Other notable features are the large recessed multiple windows, decorative stone mouldings and panels, the two flanking free-standing stone walls and the parapet wall. The interior features a central two-storey atrium with marble balustrade, double staircase and skylight, providing a spacious and elegant entrance lobby.

The open, well-lit interior is articulated by rows of free-standing columns that support a gridwork of dentilled ceiling beams. A central two-story atrium with marble balustrade, double staircase and skylight unifies the interior and provides a spacious and elegant entrance lobby that is a valuable architectural resource of the city.

Important to the preservation of the interior are the original architectural features, including but not limited to the open atrium, the marble double staircase, dado and balustrade, the skylight, the composite columns, wall pilasters and piers, the multiple windows with transoms of lavender-coloured glass, and the dentilled ceiling beams.




Image 3.5: Historical image of the Hamilton Public Library Building Interior. Source: Digital Archive Ontario, Toronto Public Library.



Image 3.6: Historical image of the Hamilton Public Library Building Interior. Source: Digital Archive Ontario, Toronto Public Library.



### 3. ASSESSMENT OF EXISTING CONDITIONS

#### 3.4 HERITAGE INTERIORS

The proposed security upgrades involve alterations to the interior of this designated heritage building therefore the focus of this HIA will be on the Main Hall space, specifically with the east stair.

The interior of the Heritage Lobby is a striking example of neo-classical principles applied to interior design, with careful massing and proportion, simple stylized decorative detailing and elegant materials. Accessed off of the main entry at Main Street W, this grand space is richly finished with marble at the columns, pilasters, double stairs and floors, and high coffered ceilings with dentilated ceiling beams.

Based on the reasons for designation listed in By-law 87-250, the interior architectural heritage features of the Main Hall and Lobby that are to be preserved are:

- The open atrium and skylight.
- Rows of floor to ceiling columns and polished marble clad pilasters, complete with highly articulated capitals.
- Gridwork of dentilated ceiling beams.
- Double marble staircase, dado, balustrade framing a large central skylight above the spacious Main Hall.
- Multiple windows with transoms of lavender-colour glass.

The floors at the Main Hall and Lobby are finished in a carrara marble tile which has a white body with grey veining. This flooring appears not to be original to the building and was more likely a part of a previous renovation, the marble selected to match the existing marble stairs, columns and pilasters. Historical images of the Main Hall appear to show a mosaic tile floor (refer to images #3.5 & 3.6 in Section 3.3).



Image 3.9: Archive photo of Main Hall interior at east stair showing original floor which appears to be mosaic.



Image 3.7: Interior view of the Main Hall space with east stair and upper atrium with skylight.




Image 3.8: Interior view of the heritage skylight above the central open space in the Main Hall.



Image 3.10: Current view of east Heritage Stair in the Main Hall with existing 12"x12" marble tile flooring.



### 3. ASSESSMENT OF EXISTING CONDITIONS

The double staircase and balustrades are the original carrara marble and the original architectural detailing has been retained. The inset marble panels at the wainscoting along the stair appears to be a different type of marble, with more dramatic veining that is black in colour rather than the grey. There is a carved marble detail in a floral/leaf motif at the front and side faces of the marble-clad newel posts at each stair.

#### 3.5 ASSESSMENT OF EXISTING CONDITIONS

Although the interiors spaces of this designated heritage building have undergone various renovations when it transformed from its original use as a library to the current function of a courthouse, much of the quality of the original interior space in the Main Hall and Lobby has survived through the years. The needs of the courthouse required enclosing a majority of the space into offices and courtrooms, yet the Lobby and Main Hall spaces have been left open, maintaining the grand scale of the original design. Currently, this space is well used as it accommodates all of the public traffic that enters into the building from the main entry at Main Street W.. This entry area currently has a security desk and screening gates for all who enter into the building. From here, one can move north towards the courtrooms or elevators going up to the other courtrooms on the upper floor. Otherwise, to the west is the enclosed court services area and to the east is the more open waiting area.

The neoclassical architectural style is characterized by grandeur of scale, simplicity of geometric forms, a dramatic use of columns and a preference in blank walls. This style is well reflected in the Lobby and Main Hall of the courthouse building. The original architectural elements that remain in the Lobby and Main Hall are the tall marble clad pilasters with highly articulated capitals, marble clad beams, marble wainscoting and the marble double stairs and balustrades, with original light fixtures at the newel posts. The marble tile floors throughout the Main Hall and cladding at the elevator walls are not original to the building.

Perhaps the most striking elements in this grand space are the two marble staircases which are located at the Lobby space and open to the Main Hall. These stairs provide access to the upper floor to a large atrium space open to below and skylight above, with courtrooms and offices beyond. The marble used for the treads, square newel posts, balusters and balustrades, base and trim banding at the wainscoting is a carrara marble with the inset marble panels of the wainscoting being of a calacatta marble, which has a more white base with dark grey/black veining. Some minor alterations have been made to the double staircases over the years, including the addition of anti-slip tape at the stair nosings and a hand sanitizer unit mounted on the east stair wall.



Image 3.11: Interior view of marble floors in the Main Hall



Image 3.12: Interior view of Heritage Stair (east).



Image 3.13: Interior view of Heritage Stair (west).



## 4. DESCRIPTION & PURPOSE OF PROPOSED ACTIVITY

### 4.1 DESCRIPTION AND PURPOSE OF PROPOSED DEVELOPMENT

The proposed interior renovations to the existing designated building's lobby space and stairs are required by the Ministry of the Attorney General (MAG) for the purposes of providing the security infrastructure necessary for the secure function of the courthouse. The proposed alterations are located in the main Lobby and Main Hall off of the existing main entry at Main Street W. This entry at Main Street W is used as the primary public entry into the courthouse, and is used by staff, attorneys and the general public. There is no alternate Courthouse entry that would allow the implementation of the security infrastructure as set out by MAG and therefore the proposed interior alterations are required.

The interior alterations that are proposed in the Main Hall and Lobby Area involve the installation of security screens, gates and screening equipment for the new screening area. The installation of a swing gate at the top and bottom of the west marble stairs is also required to provide the additional security at this area. Due to the necessary renovations to provide the secure entrance for the Courthouse functions, the area to be focused on for this heritage assessment is at the Lobby interior, specifically the original set of marble stairs. Although the proposed renovations involve the addition of a new screening area in the Lobby space, the marble floor tiles in this area are not original to the building and therefore are not included in the heritage assessment. The proposed alterations will have the most direct impact on the west set of marble stairs in this heritage space.






Image4.1: Main Floor Plan- layout by a+LiNK Architecture. Refer to Enlarged Plan in Appendices.

## 4. DESCRIPTION & PURPOSE OF PROPOSED ACTIVITY

### 4.2 THE PROPOSED LAYOUT

The partial main floor plan identified below (Image 4.2) is the current proposed design that is based on the security requirements of MAG (Enlarged Plan can be found within the Appendices). This layout provides direct access from the existing entry off of Main Street W. through to the screening area from the Lobby area the the Main Hall. The police zone is located in close proximity to the entry to allow for direct sightlines which are required for security to access incoming patrons. The proposed new security screening area has been located centrally in the Main Hall to maximize the visibility though the space, providing the optimal security requirements for MAG. The screening area is protected from the remainder of the space by glass partitions that are connected to anodized posts that are anchored to the floor. These posts require four (4) anchor bolts in order to securely and structurally anchor them to the floors. If required, these posts may be removed in the future with minimal disruption to the existing space. Being that the existing marble tiles at the Lobby area not identified heritage attributes, the direct physical impacts by the proposed alterations to the floors in this area are not included in this report.

Aside from the physical impacts, the proposed alterations could potentially alter the sightlines through the Main Hall space, with the new screens that are to be installed possibly resulting in a less open space in this large open area. In order to minimize any impacts on the sightlines though the Main Hall space the security screens are nine foot high glass partitions. The intention is to avoid closing off the Main Hall and to maintain the grand feel of the large double height space.



Images 4.2 & 4.3: Partial Main Floor and partial Second Floor plans indicating locations of proposed new swing gates - layouts by a+LiNK Architecture, February 2025



## 4. DESCRIPTION & PURPOSE OF PROPOSED ACTIVITY

The most prominent heritage elements in the Main Hall and Lobby that could potentially be most impacted by the new screening area renovations would be the east and west marble stairs. The new security gate posts located adjacent to the east stair and the new security door frame adjacent to the west stair are secured to the floor via anchor bolts in order to avoid attachments directly anchored into the marble walls of the stairs.

Additional security is provided via a turnstile swing gate that is located at the top and bottom of the west stair. The lower gate is to be located at the edge of the stair landing while the top gate is to be at the first tread at the top of the stair. These single-swing gates are required to restrict public access up these stairs from the Lobby while allowing exiting down through the stair in the case of an emergency. Due to the concern for possible damage to the existing marble staircase, several options were explored in order to minimize the number of penetrations through the marble. These are described in Section 5 of this report.

Immediately it was recognized that mounting to the vertical face of the marble newel posts was to be avoided as this alteration would be the most impactful to the heritage resource. The initial design involved a double swing gate requiring two posts which would have resulted in a total of 8 (eight) floor penetrations per gate. The type of gate that has been selected was carefully chosen in order to minimize the number of penetrations required. The proposed unit has a single swing gate that allows for only one stainless steel mounting post which is attached to the floor via three 12.5mm diameter fasteners. A fourth hole (50mm diameter) is required to bring in power to the unit for the control mechanism. This layout results in a total of approximately 4 (four) penetrations for the gate's vertical support post required for the proposed security access.



Image 4.4a: Proposed location of the new swing gate at the bottom of the west stair.




Image 4.4b: Drawing of new swing gate at the bottom of the west stair.



Image 4.5a: Proposed location of the new swing gate at the top of the west stair.




Image 4.5b: Drawing of the new swing gate at the top of the west stair.

The 168mm diameter gate post would be mounted on the marble step with a small vertical gap which would provide enough clearance from the face of the newel post to protect the marble finish and carved detail. The single gate panel is of a thick acrylic material, fastened to the cylindrical stainless steel post. It is the intention of this selection that the materiality of the post and the translucency of the gate panel result in minimal visual impact at the marble heritage stair.

There would be a total of two gates required: one at the bottom and one at the top of the east stair.

## 5. IMPACT ASSESSMENT

### 5.1 SUMMARY OF THE IMPACTS OF PROPOSED DEVELOPMENT

The interior renovations proposed in the form of security access systems in the heritage space of the Main Hall and Lobby have been reviewed in relation to their potential direct and indirect impacts. Although the new screening area centrally located within the Main Hall will make a visual impact on the space, with the addition of the security screens, the most direct impact will be to the existing marble stair in the form of the installation of a single swing gate at the top and bottom of the east stair. A total of four penetrations are required for both anchoring the vertical support for the gate as well as a penetration for power at each gate. These penetrations are unavoidable in order to provide the necessary security required by the Ministry of the Attorney General (MAG) for the courthouse.

Ultimately, any renovations to the interior of this space will have some affect on the existing cultural heritage resource. However, the proposed layout aims for these modifications to have only a minor impact relative to the overall character of the heritage features in the entry Lobby and Main Hall as well as being able to be removed in the future if required. The impact of the proposed activity to the cultural heritage resource is intended to be reversible so that it can be brought back to as close to its original condition as possible if the proposed alterations are removed at some point.

### 5.2 IMPACTS OF PROPOSED DEVELOPMENT

An impact assessment of the proposed development on the existing cultural heritage resource has been made following the principles laid out in the Standards & Guidelines for Conservation of Provincial Heritage Properties - Information Bulletin 3: Heritage Impact Assessments for Provincial Heritage Properties. The purpose of the assessment is to determine any impacts, positive, negative, direct or indirect, that the proposed activity may have on the property's cultural heritage value or interest. An impact is defined in Bulletin #3 as being *a change in an identified cultural heritage resource resulting from a particular activity*.

A direct adverse impact would have a permanent and irreversible negative affect on the cultural heritage value or interest of a property or result in the loss of a heritage attribute on all or part of the provincial heritage property. Examples of direct adverse impacts on a provincial heritage property may include, but are not limited to:

IMPACT: DIRECT ADVERSE		DESCRIPTION
REMOVAL/ DEMOLITION	Removal or demolition of all or part of any heritage attribute.	Not applicable - no heritage attributes are to be removed for the required alterations.
REMOVAL/ DEMOLITION	Removal or demolition of any building or structure on the provincial heritage property whether or not it contributes to the cultural heritage value or interest of the property (i.e. non-contributing buildings)	Not applicable - no heritage attributes are to be removed for the required alterations.

## 5. IMPACT ASSESSMENT

IMPACT: DIRECT ADVERSE		DESCRIPTION
LAND DISTURBANCE	Any land disturbance, such as a change in grade and/or drainage patterns that may adversely affect a provincial heritage property, including archaeological resources;	Not applicable - interior renovation.
ALTERATIONS	Alterations to the property in a manner that is not sympathetic, or is incompatible, with cultural heritage value or interest of the property. This may include necessary alterations, such as new systems or materials to address health and safety requirements, energy-saving upgrades, building performance upgrades, security upgrades or servicing needs;	The proposed alterations require a total of four penetrations through the marble steps of the top and bottom of the east stair. Three of these penetrations are 1/2" diameter in size for the pole mounting and one is 2" diameter in size for the power input. These holes may be repaired by professional restorers if the alterations are removed in the future.
ALTERATIONS - ACCESS	Alterations for access requirements or limitations to address such factors as accessibility, emergency egress, public access, security;	The proposed alterations are necessary to provide security for access required by the courthouse. The alterations involve the installation of glass security screens at the Main Hall and a security swing gate at the top and bottom of the east stair.
NEW CONSTRUCTION	Introduction of new elements that diminish the integrity of the property, such as a new building, structure or addition, parking expansion or addition, access or circulation roads, landscape features;	Not applicable - interior renovation.
NATURAL FEATURES	Changing the character of the property through removal or planting of trees or other natural features, such as a garden, or that may result in the obstruction of significant views or vistas within, from, or of built and natural features;	Not applicable - interior renovation. No significant views or vistas from within will be affected.
CHANGE IN USE	Change in use for the provincial heritage property that could result in permanent, irreversible damage or negates the property's cultural heritage value or interest;	Not applicable - the interior renovation supports the existing use.
INTENSIFICA- TION	Continuation or intensification of a use of the provincial heritage property without conservation of heritage attributes;	Continuation of existing use: the proposed interior renovation aims to conserve the heritage attributes of the property with minimal impact and proposed mitigation strategies.



## 5. IMPACT ASSESSMENT

An indirect adverse impact would be the result of an activity on or near the property that may adversely affect its cultural heritage value or interest and/or heritage attributes. Examples of indirect adverse impacts include, but are not limited to:

IMPACT: INDIRECT ADVERSE		DESCRIPTION
SHADOWS	Shadows that alter the appearance of a heritage attribute or change the visibility of an associated natural feature or plantings, such as a tree row, hedge or garden;	Not applicable - interior renovation.
ISOLATION	Isolation of a heritage attribute from its surrounding environment, context or a significant relationship;	No direct change to the context or any significant relationships of the heritage attribute with its surroundings.
VIBRATION	Vibration damage to a structure due to construction or activities on or adjacent to the property;	Not applicable - minimal intervention required to the interior space.
VIEWS	Alteration or obstruction of a significant view of or from the provincial heritage property from a key vantage point.;	Not applicable - the proposed interior alterations do not obstruct any significant views.

Positive impacts are those that may positively affect a property by conserving or enhancing its cultural heritage value or interest and/or heritage attributes. Examples of positive impacts may include, but are not limited to:

IMPACT: POSITIVE		DESCRIPTION
CONSERVATION	Changes or alterations that are consistent with accepted conservation principles, such as those articulated in MTCS's Eight Guiding Principles in the Conservation of Historic Properties, Heritage Conservation Principles for Land Use Planning, Parks Canada's Standards and Guidelines for the Conservation of Historic Places in Canada;	The proposed alterations to the existing cultural heritage resource involve minimal intervention to maintain the historical content of the resource. The future mitigation strategies for the proposed alterations are consistent with accepted conservation principles.
ADAPTIVE RE-USE	Adaptive re-use of a property – alteration of a provincial heritage property to fit new uses or circumstances of the of property in a manner that retains its cultural heritage value of interest;	The addition of modern security systems , including new swing gates at the east stair, would allow for continued use of the Courthouse in a safe and secure manner that is required by this use.
COMMEMORATION	Public interpretation or commemoration of the provincial heritage property.;	Not applicable.

## 6. CONSIDERED ALTERNATIVES & MITIGATION MEASURES

### 6.1 OPTIONS FOR MITIGATION - ALTERNATE LAYOUTS

The proposed design for upgraded security access at the heritage Lobby and Main Hall involves the addition of a screening area and secure access off of the building's main entry. Due to the fact that the east stair is accessed off of the Lobby area outside of the secured screening area, a new swing gate is required to be installed at the stair to control access, prohibiting people from bypassing the security checkpoint and gaining access to the building. The new screening area will require a number of penetrations to anchor the vertical supports and service penetrations through the floor. The marble tile floor in this area is not identified in the designation and therefore the impact of the new installation in the Main Hall would mainly be visual within the space. The intention is for the use of glass panel security screens to avoid impeding views through the grand space. As the majority of the heritage features in this space are at higher levels, the new screens should not hamper the enjoyment of the heritage features of the Main Hall, such as the column capitols, coffered ceilings, etc.,. The cultural heritage resource that will be directly impacted is the west marble stair with the proposed installation of a single swing gate at the top and bottom of the stair. This will require a total of four holes, three (3) 12.5mm in diameter and one (1) 50.0mm in diameter, that will penetrate the third marble stair tread, below the landing as well as the top marble tread. The selection of the single-post swing gate was based on minimizing the impact to the heritage marble stair, avoiding penetrations to the marble newel post. Refer to the appendices for more information about selected gate manufacturer/model.

Alternate design options have been reviewed extensively for their viability both from a heritage impact point of view and the security feasibility perspective. The challenge was to provide the required level of security necessary for the proposed activity while reducing the impact to the cultural heritage resource. Any alternative to be considered needed to avoid compromising the viability of the secure access requirements specified by the Ministry of the Attorney General (MAG) for the courthouse.

#### **Alternate Option 1: The Proposed Layout with Gate at Bottom Tread Only**

The floor plans show the current proposed design with the addition of a single swing gate at the bottom and top tread of the existing heritage stair. This option would eliminate the gate at the top of the stair, leaving just the one at the bottom of the stair. This alternate design reduces the overall number of penetrations by approximately 50% by reducing the number of gates. Although this option would have a lesser impact on the marble stair, there remains a risk of a breach in security.

**Total penetrations: 4 for one gate/bottom tread**

#### **Alternate Option 2: Freestanding Barrier**

An alternate option would be to place moveable (unattached) stanchions with retractable bands at the top and bottom of the stair to limit access. Although this would not require any penetrations to the marble treads, this would also pose a major risk to public safety, with potential threats to security, staff and courtroom spaces on the upper floor by not providing a more secure method of restricted access. An added risk would be the possibility of the moveable stanchion being used as a weapon which could result in potential bodily harm to the public or staff.




Image 8.1: Partial Ground Floor plan showing Alternate Option 1 layout, by a+LiNK Architecture.

## 6. CONSIDERED ALTERNATIVES & MITIGATION MEASURES

### **Alternate Option 3: Removal of Marble Stair Treads**

A second option would be to remove the existing stair tread where the attachments are required and replace with a similar marble tread. The removed treads would then be stored until such time as the alterations would be removed and the space returned to its original condition. This option is not recommended as it is highly unlikely that the marble treads would not be damaged or broken during the process of removal. Even if the treads were removed in one piece, the other issue would be with long-term storage of the treads. There is a risk that these treads may be damaged or lost while in storage. Ultimately, the best conservation is with minimal intervention which would include avoiding the dismantling of the historic fabric.

### **Alternate Option 4: Do nothing**

The last option would be to do nothing, leaving the heritage stair as it currently is, without any further intervention. Without the required security measures, there would be a higher risk of a breach in security, with unrestricted access both at the top and bottom of the stair. This would result in unrestricted access through the two floors and would pose a risk to public safety, with potential threats to security to the courtroom spaces on the upper floor. It may be possible to place guards at either the top or bottom of the stair to monitor access, however, this may be a less feasible option with the lack of available manpower to provide the necessary security. It was discussed at subsequent meeting to have Police / Security monitor the stair, however Police advised that this would not be possible. In the event that Police are called to an event within the building while still maintaining supervision over the incoming patrons it would not be possible to monitor access at the stair.

## 6.2 SUMMARY OF ALTERNATIVES

The interior renovations required by MAG in the form of security access systems in the Lobby will directly impact the existing cultural heritage resource by requiring alterations to the existing marble stair to the west of the main entry. As the proposed layout will require a total of 8 penetrations at the marble treads of the heritage stair, alternate options were studied in order to minimize or eliminate penetrations through the marble. Since this original carrara marble stair is considered to be of heritage value as it demonstrates the extensive use of costly materials and quality of craftsmanship, it is important to preserve this cultural heritage resource and minimize any damage, if possible. The proposed screening area located in the Main Hall will have minimal visual impact to the heritage resource as most of the heritage features are located above the height of the panels, which are glass to allow for views through the space.

The potential heritage impact of the proposed interior renovations on the designated built heritage resource has been assessed and alternate options have been reviewed. The aim of the alternate options was to provide the required security access while reducing the number or eliminating the need for penetrations through the marble stair treads. In most options, several penetrations are still required for both anchoring the vertical supports for the gates as well as some penetrations for services. Option 1 provided the required security but still required a number of penetrations. Option 2 involved the removal and storage of the affected marble floor treads, which was not a viable option as it was highly unlikely that the treads would be removed cleanly or the risk of the treads being damaged or lost during storage. Finally, Option 3 'Do Nothing', would leave the existing marble stair untouched but would result in a possible risk of a breach in security by not restricting access through the stair. This option is not feasible in order for the courthouse to operate securely.

Ultimately, any required security renovations to the heritage stair will have some affect on the existing marble treads. The key to having the least impact on the existing cultural heritage resource is to follow comprehensive mitigation strategies for the repair of the marble treads in the future when the proposed alterations are no longer required and can be removed.



## 6. CONSIDERED ALTERNATIVES & MITIGATION MEASURES

### 6.3 MITIGATION MEASURES

As shown in the previous section, both the proposed and alternate design option 1 involve penetrations to the existing marble treads at the heritage stair. The potential damage to the marble floors by the proposed penetrations may potentially be less adverse to the full removal of the marble tiles. That being said, a plan for the tread repairs is required for when the gates are removed in the future. This would involve a relatively minor restoration of the marble, including patching and polishing of the two treads that required the penetrations. The approach taken for marble repairs would be done by certified restoration specialists with experience in heritage marble restoration. A heritage marble preservation specialist would monitor the security installation and document each hole, preserving the marble dust, to ensure that future repairs can be made utilizing exact marble colouring resulting in the proper restoration of the cultural heritage resource. A mock up of test patches would be required for review and approval before proceeding with the work. Due to the relatively minor scope of the alterations, an accredited Conservator would not be required for the repair work.

#### MARBLE REPAIR STRATEGIES

##### Methods for Small Hole Repairs:

a) **Marble Dust Aggregate:** this repair uses the existing marble fragment materials and mixed with a non-yellowing epoxy matrix to create a patching mortar to repair smaller holes, less than 1" in diameter, in the future (Refer to image 8.2). The process would involve the following:

1. Salvaging and collecting the marble dust and fragments produced when drilling holes into the existing marble treads.
2. Each hole to be bagged, labelled, and stored in a secure location, preferably on site for future use. Documentation of what is stored is to be kept on site; to be coordinated with the BGIS Facility Manager.
3. A floorplan identifying the location of each bag is to be provided to the owner and a copy is to be stored with the bagged contents.

In the future, when the holes need to be repaired the contents of each bag is to be mixed with a non-yellowing epoxy and inserted into the prepared holes in the floor. Once dry the repair patch is to be ground and polished smooth to suit the surrounding marble. The complete stripping and refinishing of the entire tread would be required to ensure a uniform appearance once repaired. This is common form of floor maintenance and does not have a negative impact on the marble.

##### Methods for Larger Hole (1-3") Repairs:

a) **Marble Plugs:** core the 2" hole using a diamond hole saw, gather the chips and dust along with the 2" marble core (plug). This would be labeled accordingly for future repair should that be necessary. The repair would be similar to the small holes, the marble core would be set in non-yellowing epoxy resin with the chips and dust mixed to fill the void between the plug and the surrounding stair tread.




Image 8.2: Marble Dust Aggregate detail

#### Note:

The original marble treads (circa 1913) appear to be White Bianco Carrara marble from Italy. White Bianco Carrara marble has been quarried in Italy for over 2000 years. However, the colour of the stone currently obtained is not the same today as it was in the past history. This phenomenon is inherent with all naturally sourced materials and is to be expected. While the colour and pattern of this marble today are similar to the original, there would be a slight colour and pattern differential that would be observable upon close inspection. However, the general overall appearance would be cohesive and uniform through the entire stair.

## 6. CONSIDERED ALTERNATIVES & MITIGATION MEASURES

### 6.4 SUMMARY OF MITIGATION

The proposed interior renovations to the Heritage Lobby space at the Unified Family Courthouse, a Provincial Heritage Property, are required by the Ministry of the Attorney General (MAG) for the purposes of providing the security infrastructure required for the courthouse. These renovations will have the most impact on the existing historical marble treads at the east stair.

The anchoring of the new 168mm diameter stainless steel posts required for the single swing gates will require three 1/2" and one 2" diameter holes to be drilled through the existing marble treads at the top and bottom of the east stair. Each cylindrical post will be mounted to the floor with three embedded anchor bolts at the circular steel base plate. An additional hole will be required to provide power and data that will be run through the floor via a conduit. The designs presented in Section 6.1 show different options that were explored for reducing the number of penetrations, all with their own set of advantages and disadvantages. Upon review, it was concluded that there is no viable option where penetrations through the marble treads can be avoided in order to provide the security levels required by MAG for the courthouse operations.

The main concern regarding the proposed renovations is the potential long term effect on the heritage marble treads. If in the future the alterations were not required and removed from the space, the remaining holes made in the marble would need to be patched. Epoxy patch repairs are a common method of repairing holes with a maximum diameter of 1" in marble. In the case of the heritage stair, the colour and consistency of the marble, believed to be White Bianca Carrara, would allow the marble dust aggregate repair to hide the patches well.

It is noted that any variation in the marble repairs should not be perceived as a problem when viewing the heritage stairs and the lobby in its overall grandeur and wonder. The repairs noted above would be minor in scale and would not detract from the overall experience of the heritage marble stairs and the grand lobby in which they are located.

## 7. RECOMMENDATIONS

### 7.1 RECOMMENDATIONS

The purpose of this report is to assess the impact of the proposed development on the built heritage resource and recommend mitigative measures to conserve the heritage attributes of that resource. The proposed design for the required security and surveillance upgrades that are necessary for the safe operation of the Unified Family Courthouse has been reviewed and the extent of the potential damage due to penetrations at the existing marble stair treads has been identified. Alternate designs to mitigate the extent of adverse impact to the floors have been studied and evaluated to see if they were viable options for the intended use. Ultimately, there is no viable option that does not involve penetrations through the marble stair treads. Based on which design most fulfills the requirements of the required security upgrades, the original design outlined in Section 6 of this report should be pursued subject to the mitigation measures recommended below. This approach presents the best option to mitigating impacts to the built heritage resource while maintaining project viability.

Moving forward, the following recommendations for conservation/mitigation measures focus on ensuring that the holes in the marble treads of the heritage stair are executed in the least invasive methods possible with the possibility of reversibility of the proposed alterations in the future:

#### **Execution of Proposed Alterations**

In order to minimize the adverse impact of the proposed development, a marble specialist with demonstrated experience on heritage buildings, shall:

- Review the plan for hole locations prior to drilling, perform the drilling and document & store the marble dust according to a site map of the hole locations.
- During the alterations, the surrounding marble treads and floors are to be protected in order to avoid any remedial damage.
- Care is to be taken that the proper equipment is used in order to ensure that the holes are cut in a clean and concise manner without damaging the surrounding marble stair.
- Ensure that the holes that are made through the marble are no larger than the size required for the required purpose and adequate space from a tread edge is maintained to avoid chipping.

#### **Remediation + Restoration**

In the event that the alterations to the heritage marble stair are to be removed in the future, the marble floors will require patching and repair. For this work the following steps should be taken:

- A restoration specialist or Conservator with experience in heritage marble restoration retained.
- Mock-ups of the proposed repairs to be completed on a marble similar in colour.
- Test patching to be completed on an inconspicuous area of the floor for final review and approval before proceeding with the restoration work.
- Once an approved method has been signed off the heritage marble restoration specialist will then carry out the repairs with all penetrations.
- It is recommended that all of the stair treads to be polished and re-sealed to provide the best overall finish.

## 7. RECOMMENDATIONS

### **Heritage Impact Assessment + Conservation Plan**

Prior to any restoration work being done, a Heritage Impact Assessment (HIA) may be required to review mitigation options. A Marble Conservation and Restoration Plan would be conducted at that time to provide current restoration methods and material available. If the proposed alterations are planned to be in place for ten years or more, there may be improvements in the restoration process.

The Marble Conservation and Restoration Plan would outline would be completed if the security measures are removed in the future and marble restoration is undertaken. At that time the plan would also review what new technologies may be available and best suited for the repair of the heritage marble stairs.

---

# APPENDICES

---

# APPENDIX A: References

# REFERENCES

## Province of Ontario Documents

1. Ministry of Heritage, Sport, Tourism and Culture Industries. *Standards and Guidelines for Conservation of Provincial Heritage Properties*. April 2010.
2. Ministry of Tourism, Culture and Sports. *Standards and Guidelines for Conservation of Provincial Heritage Properties- Information Bulletin #3-Heritage Impact Assessment for Provincial Heritage Properties*. 2017.
3. Her Majesty the Queen in Right of Canada. *Standards and Guidelines for the Conservation of Historic Places in Canada*. Second Edition. 2010.
4. Ministry of Municipal Affairs and Housing. *Ontario Provincial Policy Statement, Under the Planning Act*. 2014, 2020.
5. Ontario Ministry of Culture. *Heritage Resources in the Land Use Planning Process, Cultural Heritage and Archaeology Policies of the Ontario Provincial Policy Statement*. 'Info Sheet #5, Heritage Impact Assessments and Conservation Plans.' 2005.
6. Ontario Ministry of Culture. *Ontario Heritage Toolkit: Heritage Property Evaluation*. 2006.
7. The Planning Act and Provincial Policy Statement (PPS) 2024
8. The Ontario Heritage Act (OHA)

## Municipal Documents

1. City of Hamilton. *City of Hamilton Register of Property of Cultural Heritage Value or Interest*. June 2017.
2. City of Hamilton. *By-Law No. 87-250 - Designation of property at 55 Main Street West, September 1987*.
3. City of Hamilton. *Urban Hamilton Official Plan, Volume 2*. January 2022.
4. City of Hamilton. *The Downtown Hamilton Secondary Plan, August 14, 2019*.
5. City of Hamilton. *Hamilton's Heritage Volume 5, June 2005*.

## Other

1. Unified Family Courthouse Security Upgrades: *drawing set by a+LiNK architects*. February 2025.
2. Map Images: *Hamilton, Ontario*. Google Maps. November/March 2022.
3. Historical renderings and photographs, *Digital Archive Ontario*
4. Interior photographs, *a+LiNK architecture*, October 2021.
5. Marble restoration: *Marble Restoration Services Ltd., Ottawa*. [www.marblerestoration.ca](http://www.marblerestoration.ca)

# APPENDIX B : Project Personnel





## ED VAN DER MAAREL

### PRINCIPAL ARCHITECT + PARTNER + HERITAGE CONSULTANT

Dip. Arch., Dip. Arch.Tech., OAA, CAHP

Ed is Partner, CEO and Principal Architect of a+LiNK Architecture and is responsible for the design of heritage restoration, preservation and adaptive reuse projects. Ed has led a variety of complex renovation, addition, and adaptive reuse projects over the last 35 years. Ed is the firm's heritage specialist and strongly supports adaptive reuse, restoration and preservation projects in order to provide our communities with a sense of place. He began his studies by completing an Architectural Technology Diploma at Fanshawe College of Applied Arts and Technology in London. Ed furthered his studies by graduating from The Royal Architectural Institute of Canada Syllabus Program in Vancouver (RAIC). Ed is widely known in the heritage community for the restoration of the Canada Southern Railway Station in St. Thomas, which became an award-winning restoration project.

### EDUCATION

- Graduate of the Royal Architectural Institute of Canada (RAIC) Syllabus Program, Vancouver, B.C.
- Diploma Architectural Technology, Fanshawe College of Applied Arts and Technology, CAD Programming
- OAA Professional Development, Ongoing

### PROFESSIONAL ASSOCIATIONS

- Registered Architect, Ontario Association of Architects
- Heritage Consultant, Canadian Association of Heritage Professionals
- Member, Community Heritage Ontario
- Member, Architectural Conservancy of Ontario
- Member, Heritage Canada Foundation

### PUBLIC ACTIVITIES

- Board Member, On Track St. Thomas (St. Thomas Elevated Park)
- Past Director, North America Railway Hall of Fame
- Committee Member, St. Thomas RAILS (promoting St. Thomas as the Railway Capital of Canada)
- Ontario Visual Heritage Committee, Elgin County
- Speaker, Architectural Conservancy of Ontario for Heritage
- Past Chairman, St. Thomas Local Architectural Conservation Advisory Committee

**Responsibilities:** Coordinate communication of project team and client team, manage and oversee project team throughout design + construction documentation, and oversee contract administration.

### SELECTED EXPERIENCE

#### HERITAGE

- Canada Southern Railway Station Adaptive Reuse + Restoration, St. Thomas, ON
- Eldon House Restoration, London, ON
- RBJ Schlegel Park Heritage House Adaptive Reuse, Kitchener, ON
- City of St. Thomas Heritage Conservation District, St. Thomas, ON
- City of Kincardine Heritage Conservation District, Kincardine, ON
- St. Thomas Elevated Park (STEP), St. Thomas, ON
- Banting House Museum, London, ON
- Grosvenor Lodge Restoration, London, ON
- Colborne Building Roof Stabilization + Adaptive Reuse, London, ON
- City of London Heritage Conservation District, London, ON
- John Sopinka Courthouse Restoration, Hamilton, ON
- Unified Family Courthouse Security Upgrades, Hamilton, ON
- Elgin County Railway Museum, St. Thomas, ON
- Red Antiquities Building, London, ON
- City of London Heritage Condition Assessment, 13 Heritage Buildings
- Victoria Park Cenotaph Restoration, London, ON
- City of London T-Block Restoration, London, ON
- Petrolia Post Office Renovations and Restoration, Petrolia, ON
- Brantford Gaol Restoration, Brantford, ON
- Elsie Perrin Williams Estate Restoration, London, ON
- Cayuga Courthouse Restoration, Cayuga, ON
- Pinafore Park Dance Pavilion, St. Thomas, ON
- Stratford Gaol Restoration, Stratford, ON
- City of London Park Farm Restoration, London, ON
- Flint Cottage, London, ON



## ALICIA LESNIAK

### ARCHITECT

B. Arch., B. E.S.

Alicia is an experienced Architect with the Ontario Association of Architects with a passion for architecture with experience ranging from small-scale commercial and residential to large-scale commercial and institutional buildings. With experience in British Columbia, Yukon, and Ontario including Toronto and London, Alicia brings a breadth of experience in designing, coordinating, developing and managing projects as Design Lead through all design and construction stages. By balancing the design intent and the reality of site conditions, with budgetary and functional needs, Alicia provides her expertise in project management in order to satisfy client and project goals. Alicia also specializes in providing Heritage Impact Assessments for various project types as per municipal requirements.

### EDUCATION

- Bachelor of Architecture, University of Waterloo, 1993
- Bachelor of Environmental Studies, University of Waterloo, 1991
- OAA Professional Development, Ongoing

### PROFESSIONAL ASSOCIATIONS

- Registered Architect, Ontario Association of Architects

### PUBLIC ACTIVITIES

- Committee Member, London Society of Architects

**Responsibilities:** Assist with design and planning, attend client design meetings, lead + coordinate sub-consultants throughout design, construction documentation + contract administration.

### SELECTED EXPERIENCE (*\*Prior to joining a+LiNK*)

#### HERITAGE

- 344-360 Talbot Street Heritage Impact Assessment, St. Thomas, ON
- 788 + 792 Dundas Street East Heritage Impact Assessment, London, ON
- 672 Hamilton Road Heritage Impact Assessment, London, ON
- 34 The Ridgeway Heritage Impact Assessment, London, ON
- 1 Cathcart Street (HIA), London
- 920-930 Dundas Street (HIA), London

#### COMMUNITY + INSTITUTIONAL

- Tillsonburg Community Centre Addition + Renovation, Tillsonburg, ON
- Tillsonburg Splash Pad, Tillsonburg, ON
- Lennoxville Curling Club, Sherbrooke, QC
- Thames Valley District School Board, Various Schools, London, ON\*
- New Learning Commons Yukon College, Whitehorse, YT\*
- School Replacement I&II, FH Collins Secondary School, Whitehorse, YT\*
- New Classroom Modularity, Ecole Emilie Tremblay, Whitehorse, YT\*
- The Clubhouse at Bowen Island Golf Course, Bowen Island, BC\*
- Art + Margaret Fry Recreational Facility (BCA), Whitehorse, YT\*

#### RESIDENTIAL

- 34 The Ridgeway Multi-Residential Infill Development, London, ON
- 300-306 Princess Ave. Multi-Residential Infill Development, London, ON
- 551-111 Waterloo Street Multi-Residential Infill Development, London, ON
- Maitland Ave. Multi-Residential Infill Development, London, ON
- Elias St. Multi-Residential Infill Development, London, ON
- Whetter Avenue Non-Profit Housing, London, ON\*
- Vipond Residence, Collingwood, ON\*
- Central Park Low Impact Residential Development, Whitehorse, YT\*
- Nelson Landing Lakefront Mixed Use Development, Nelson, BC\*

# APPENDIX C : Property Designation

## The Corporation of the City of Hamilton

BY-LAW NO. 87- 250

To Designate:

THE PROPERTY LOCATED AT MUNICIPAL NO. 55 MAIN STREET WEST

As Property of:

HISTORIC AND ARCHITECTURAL VALUE AND INTEREST

**WHEREAS** the Council of the City of Hamilton did give notice of its intention to designate the property mentioned in section 1 of this by-law in accordance with subsection 29(3) of The Ontario Heritage Act, R.S.O. 1980, Chapter 337;

**AND WHEREAS** no notice of objection was served on the City Clerk as required by subsection 29(5) of the said Act;

**AND WHEREAS** it is desired to designate the property mentioned in section 1 of this by-law in accordance with clause 29(1)(a) of the said Act.

**NOW THEREFORE** the Council of The Corporation of the City of Hamilton enacts as follows:

1. The property located at Municipal No. 55 Main Street West and more particularly described in schedule "A" hereto annexed, is hereby designated as property of historic and architectural value and interest.

2. The City Solicitor is hereby authorized and directed to cause a copy of this by-law, together with reasons for the designation set out in schedule "B", to be registered against the property affected in the proper registry office.

3. The City Clerk is hereby authorized and directed,

- (i) to cause a copy of this by-law, together with reasons for the designation to be served on the owner and The Ontario Heritage Foundation by personal service or by registered mail;
- (ii) to publish a notice of this by-law in a newspaper having general circulation in the Municipality of the City of Hamilton, for three consecutive weeks.

PASSED this 1st day of September, A.D. 1987.

  
City Clerk

  
Mayor



SCHEDULE "A"

To

By-law No. 87- 250  
55 Main Street West,  
Hamilton, Ontario

ALL AND SINGULAR that certain parcel or tract of land and premises situate, lying and being in the City of Hamilton, in the Regional Municipality of Hamilton-Wentworth and being composed of all of Lot 69 and part of Lots 50, 51, 52, 67 and 68, P.H. Hamilton Survey, Unregistered Plan, in the block bounded by Main Street, MacNab Street, Jackson Street, and Charles Street, (now closed by City of Hamilton By-law No. 9246, registered as Instrument No. 152827 H.L.), shown as Parts 1, 2 and 3 on Plan 62R-5764.

## SCHEDULE "B"

To

By-law No. 87-250

## REASONS FOR DESIGNATION

55 Main Street West,

Hamilton, Ontario

The Carnegie Building at 55 Main Street West was built in 1913 as Hamilton's main public library and is currently, in 1986, in the process of being converted into the province's Unified Family Courts.

Located directly east of City Hall, the Carnegie Building is a significant component in Hamilton's redeveloped Civic Square block, providing an imposing architectural presence as well as a valued historic dimension to the complex.

As one of more than a hundred libraries built in Ontario by philanthropist Andrew Carnegie during the early 20th Century, the Hamilton building is considered to be one of the finest in the province. Having served as the main public library for 67 years, the building is an important landmark of the city's cultural heritage; it is particularly significant as one of the few historic civic buildings still standing in Hamilton.

Local architect A. W. Peene won the international competition for the new library which is considered to be his best work in the city.

Limestone ashlar was used in the construction, following local building tradition, and the structure was given a prominent site, set back from the street and raised on a grassy bank, with a formal central stairway providing the approach.

Designed in the neo-classical style of architecture, 55 Main Street West displays a forceful composition of classical features, an imposing monumentality and a formal symmetry that are hallmarks of major public buildings of the period. The design displays a stripped or stylized version of classical detailing.


Important to the preservation of the three stone facades are the building's original features, including but not limited to the two-story pilasters, massive corner piers, the entablature with dentilated cornice, the projecting front entranceway, the large recessed multiple windows, the decorative stone mouldings and panels, the exterior stairways and doors, the two flanking free-standing stone walls and the parapet wall.

The Carnegie Corporation's stipulation that the space inside the building be kept unobstructed was successfully followed in the Hamilton library. The open, well-lit interior is articulated by rows of free-standing columns

that support a gridwork of dentilated ceiling beams. A central two-story atrium with marble balustrade, double staircase and skylight unifies the interior and provides a spacious and elegant entrance lobby that is a valuable architectural resource of the city.

Important to the preservation of the interior are the original architectural features, including but not limited to the open atrium, the marble double staircase, dado and balustrade, the skylight, the composite columns, wall pilasters and piers, the multiple windows with transoms of lavender-coloured glass, and the dentilated ceiling beams.




<div style="display: flex; justify-content: space-between;"><div style="writing-mode: vertical-rl; transform: rotate(180deg);">FOR OFFICE USE ONLY</div><div><div style="font-size: 2em; font-weight: bold;">429246 C.D.</div><div style="font-size: 0.8em;">NUMBER CERTIFICATE OF REGISTRATION</div><div style="font-size: 1.2em; margin-top: 10px;">1987 SEP 25 P 3:38</div><div style="font-size: 0.8em; margin-top: 10px;">WENTWORTH NO. 62 HAMILTON LAND REGISTRAR</div></div></div>		(1) Registry <input checked="" type="checkbox"/> Land Titles <input type="checkbox"/>		(2) Page 1 of 5 pages		
		(3) Property Identifier(s)		Block	Property	Additional: See Schedule <input type="checkbox"/>
		(4) Nature of Document Designating By-law				
		(5) Consideration Nil Dollars \$ --				
		(6) Description All of Lot 69 and Part of Lots 50, 51, 52, 67, 68, P.H. Hamilton Survey, Unregistered Plan Parts 1, 2 and 3 on Plan 62R-5764 City of Hamilton The Regional Municipality of Hamilton- Wentworth  As described in 355356 C.D.  (see Schedule "A" of By-law 87-250)				
New Property Identifiers  Additional: See Schedule <input type="checkbox"/>		(7) This Document Contains:		(a) Redescription New Easement Plan/Sketch <input type="checkbox"/>	(b) Schedule for: Description <input checked="" type="checkbox"/> Additional Parties <input type="checkbox"/> Other <input type="checkbox"/>	
Executions  Additional: See Schedule <input type="checkbox"/>						
(8) This Document provides as follows:  <div style="text-align: center; padding: 20px;">By-law No. 87-250, attached.</div> <div style="text-align: right;">Continued on Schedule <input type="checkbox"/></div>						
(9) This Document relates to instrument number(s) 355356 C.D.						
(10) Party(ies) (Set out Status or Interest)						
Name(s)		Signature(s)		Date of Signature Y M D		
The Corporation of the City of Hamilton						
(Applicant)						
By its Solicitor,				1987 09 24		
P.M. Eker						
(11) Address for Service 71 Main St. W., Hamilton, Ontario. L8N 3T4						
(12) Party(ies) (Set out Status or Interest)						
Name(s)		Signature(s)		Date of Signature Y M D		
(13) Address for Service						
(14) Municipal Address of Property 55 Main Street West Hamilton, Ontario L8P 1H4		(15) Document Prepared by: K. A. Rouff City Solicitor The Corporation of the City of Hamilton City Hall, 71 Main St. W. Hamilton, Ontario. L8N 3T4		Fees and Tax		
				Registration Fee	16.00	
				ENTRY		
				Total		



# APPENDIX D : Drawings


SECURITY HATCH LEGEND	
HATCH	DESCRIPTION
	PUBLIC ACCESS SPACES
	PRIVATE ACCESS SPACES
	SECURED ACCESS SPACES
	PARKING
	MECHANICAL & ELECTRICAL
	HIGH SECURITY
	PRISONER PATH OF TRAVEL



2  
SC2.1 SC2.1 SCALE: 1:200  
GROUND FLOOR PLAN



3  
SC2.1 SC2.1 SCALE: 1:200  
SECOND FLOOR PLAN



1  
SC2.1 SC2.1 SCALE: 1:200  
BASEMENT FLOOR PLAN

5	ISSUED FOR 99% CLIENT REVIEW	2025.02.13
4	ISSUED FOR 99% CLIENT REVIEW	2024.12.09
3	ISSUED FOR 66% REV CLIENT REVIEW	2024.08.16
2	ISSUED FOR 66% CLIENT REVIEW	2024.03.13
1	ISSUED FOR 33% CLIENT REVIEW	2023.11.14
No	Revisions	Date

Orientation

Seal

The Contractor shall check and verify all dimensions and report all errors and omissions to the IO-Owner's/MBS Designee (as applicable) for his/her written direction before proceeding with the Work.

A

B

A Detail No

B Sheet No where detailed



Colliers  
Project Leaders

**a+LiNK**  
architecture inc.  
preserve + create + sustain  
P 519.649.0220 www.aLiNKarch.ca  
362 DUFFERIN AVENUE, LONDON ON N6B 1Z4



AMIS N B


Project  
UNIFIED FAMILY COURTHOUSE  
SECURITY UPGRADES

Location  
55 MAIN ST. WEST  
HAMILTON, ONTARIO  
IO Project No. 1102795 Site No. Building No.  
Client

Drawing Title  
SECURITY REFERENCE FLOOR PLANS


Scale AS NOTED	Date 2025.02.13
Drawn by BA	Substantial Performance Date
Designed by —	Drawing No SC2.1 of 16
Approved by	CADD File NAME






2 GROUND FLOOR PLAN

A2.1 A2.1 SCALE: 1:200



1 BASEMENT FLOOR PLAN

A2.1 A2.1 SCALE: 1:200



3 SECOND FLOOR PLAN

A2.1 A2.1 SCALE: 1:200

No	Revisions	Date
5	ISSUED FOR 99% CLIENT REVIEW	2025.02.13
4	ISSUED FOR 99% CLIENT REVIEW	2024.12.09
3	ISSUED FOR 66% REV CLIENT REVIEW	2024.08.16
2	ISSUED FOR 66% CLIENT REVIEW	2024.03.13
1	ISSUED FOR 33% CLIENT REVIEW	2023.10.13

Orientation

Seal

a+Link PROJECT NO: 1953A

The Contractor shall check and verify all dimensions and report all errors and omissions to the IO-Owner's/MBS Designee (as applicable) for his/her written direction before proceeding with the Work.

A	A Detail No
B	B Sheet No where detailed



Colliers  
Project Leaders

**a+LiNK**  
architecture inc.  
preserve + create + sustain

P 519.649.0220 [www.aLiNKarch.ca](http://www.aLiNKarch.ca)  
362 DUFFERIN AVENUE, LONDON ON N6B 1Z4



AMIS

N

B

Project  
**UNIFIED FAMILY COURTHOUSE  
SECURITY UPGRADES**


Location  
**55 MAIN ST. WEST  
HAMILTON, ONTARIO**

IO Project No. **1102795** Site No. Building No.

Client  
**COLLIERS PROJECT LEADERS**

Drawing Title  
**FLOOR PLANS**

Scale AS NOTED	Date 2025.02.13
Drawn by BA	Substantial Performance Date
Designed by —	Drawing No <b>A2.1</b> of 16
Approved by	CADD File NAME



2  
A2.2 | A2.2  
SCALE: 1:100

RESERVED

1  
A2.2 | A2.2  
SCALE: 1:100

BASEMENT FLOOR PLAN

3	ISSUED FOR 99% CLIENT REVIEW	2025.02.13
2	ISSUED FOR 99% CLIENT REVIEW	2024.12.09
1	ISSUED FOR 66% REV. CLIENT REVIEW	2024.08.16
No	Revisions	Date

Orientation

Seal

a+Link PROJECT NO: 1953A

The Contractor shall check and verify all dimensions and report all errors and omissions to the IO-Owner's/MBS Designee (as applicable) for his/her written direction before proceeding with the Work.

A Detail No  
B Sheet No where detailed



**a+LINK**  
architecture inc.  
preserve + create + sustain  
P 519.649.0220 [www.aLiNKarch.ca](http://www.aLiNKarch.ca)  
362 DUFFERIN AVENUE, LONDON ON N6B 1Z4



AMIS N B

Project  
UNIFIED FAMILY COURTHOUSE  
SECURITY UPGRADES


Location  
55 MAIN ST. WEST  
HAMILTON, ONTARIO  
IO Project No. Site No. Building No.  
1102795

Client  
COLLIERS PROJECT LEADERS

Drawing Title  
BASEMENT FLOOR PLAN

Scale AS NOTED	Date 2025.02.13
Drawn by BA	Substantial Performance Date
Designed by —	Drawing No A2.2 of 16
Approved by	CADD File NAME





2  
A2.3 | A2.3  
SCALE: 1:100

1  
A2.3 | A2.3  
SCALE: 1:100

No	Revisions	Date
5	ISSUED FOR 99% CLIENT REVIEW	2025.02.13
4	ISSUED FOR 99% CLIENT REVIEW	2024.12.09
3	ISSUED FOR 66% REV CLIENT REVIEW	2024.08.16
2	ISSUED FOR 66% CLIENT REVIEW	2024.03.13
1	ISSUED FOR 33% CLIENT REVIEW	2023.11.14

Orientation

Seal

a+Link PROJECT NO: 1953A

The Contractor shall check and verify all dimensions and report all errors and omissions to the IO-Owner's/MBS Designee (as applicable) for his/her written direction before proceeding with the Work.

A	A Detail No
B	B Sheet No where detailed



Colliers  
Project Leaders

**a+LiNK**  
architecture inc.  
preserve + create + sustain  
P 519.649.0220 [www.aLiNKarch.ca](http://www.aLiNKarch.ca)  
362 DUFFERIN AVENUE, LONDON ON N6B 1Z4



AMIS N B

Project  
UNIFIED FAMILY COURTHOUSE  
SECURITY UPGRADES


Location  
55 MAIN ST. WEST  
HAMILTON, ONTARIO  
IO Project No. 1102795 Site No. Building No.

Client  
COLLIERS PROJECT LEADERS

Drawing Title  
GROUND FLOOR PLAN

Scale AS NOTED	Date 2025.02.13
Drawn by BA	Substantial Performance Date
Designed by —	Drawing No A2.3 of 16
Approved by	CADD File NAME





2  
A2.4 | A2.4  
RESERVED  
SCALE: 1:100

1  
A2.4 | A2.4  
SECOND FLOOR PLAN  
SCALE: 1:100

No	Revisions	Date
5	ISSUED FOR 99% CLIENT REVIEW	2025.02.13
4	ISSUED FOR 99% CLIENT REVIEW	2024.12.09
3	ISSUED FOR 66% REV CLIENT REVIEW	2024.08.16
2	ISSUED FOR 66% CLIENT REVIEW	2024.03.13
1	ISSUED FOR 33% CLIENT REVIEW	2023.11.14

Orientation

Seal

The Contractor shall check and verify all dimensions and report all errors and omissions to the IO-Owner's/MBS Designee (as applicable) for his/her written direction before proceeding with the Work.

A	A Detail No
B	B Sheet No where detailed



**a+LiNK**  
architecture inc.  
preserve + create + sustain  
P 519.649.0220 [www.aLiNKarch.ca](http://www.aLiNKarch.ca)  
362 DUFFERIN AVENUE, LONDON ON N6B 1Z4



AMIS N B

Project  
**UNIFIED FAMILY COURTHOUSE  
SECURITY UPGRADES**


Location  
55 MAIN ST. WEST  
HAMILTON, ONTARIO

IO Project No. 1102795 Site No. Building No.

Client  
**COLLIERS PROJECT LEADERS**

Drawing Title  
**SECOND FLOOR PLAN**

Scale AS NOTED	Date 2025.02.13
Drawn by BA	Substantial Performance Date
Designed by —	Drawing No <b>A2.4</b> of 16
Approved by	CADD File NAME



1  
A2.2 | A5.1  
SCALE: 1:25  
BASEMENT ENLARGED PLAN

5	ISSUED FOR 99% CLIENT REVIEW	2025.02.13
4	ISSUED FOR 99% CLIENT REVIEW	2024.12.09
3	ISSUED FOR 66% REV CLIENT REVIEW	2024.08.16
2	ISSUED FOR 66% CLIENT REVIEW	2024.03.13
1	ISSUED FOR 33% CLIENT REVIEW	2023.11.14
No	Revisions	Date

Orientation

Seal

a+Link PROJECT NO: 1953A

The Contractor shall check and verify all dimensions and report all errors and omissions to the IO-Owner's/MBS Designee (as applicable) for his/her written direction before proceeding with the Work.

A	A Detail No
B	B Sheet No where detailed

Colliers  
Project Leaders

preserve + create + sustain

P 519.649.0220      www.aLiNKarch.ca  
362 DUFFERIN AVENUE, LONDON ON N6B 1Z4



AMIS      N      B

Project  
UNIFIED FAMILY COURTHOUSE  
SECURITY UPGRADES

Location  
55 MAIN ST. WEST  
HAMILTON, ONTARIO


ID Project No.      Site No.      Building No.  
1102795

Client  
COLLIERS PROJECT LEADERS

Drawing Title  
ENLARGED FLOOR PLAN DETAILS

Scale AS NOTED	Date 2025.02.13
Drawn by BA	Substantial Performance Date
Designed by —	Drawing No A5.1 of 16
Approved by	CADD File NAME





### PARTITION TYPE LEGEND

SYM.	DESCRIPTION
P1	PARTITION WALL - SOLID SURFACE HALF WALL: - 6mm QUARTZ - 19mm BALTIC BIRCH PLYWOOD - 92mm 20 ga. METAL STUDS @ 400mm o.c. - 19mm BALTIC BIRCH PLYWOOD - 6mm QUARTZ
P2	PARTITION WALL - GLAZED BARRIER - 12mm MONOLITHIC 2745mm HIGH TEMPERED GLASS PANELS ON 2440mm HIGH BRUSHED SS POST SYSTEM (KLARITY PARTITION SYSTEM - KPOSTBS)

RESERVED

2  
A5.2 | A5.2

SCALE: 1:25

MAIN ENTRANCE SECURITY BARRIER

1  
A2.3 | A5.2

SCALE: 1:25

5	ISSUED FOR 99% CLIENT REVIEW	2025.02.13
4	ISSUED FOR 99% CLIENT REVIEW	2024.12.09
3	ISSUED FOR 66% REV. CLIENT REVIEW	2024.08.16
2	ISSUED FOR 66% CLIENT REVIEW	2024.03.13
1	ISSUED FOR 33% CLIENT REVIEW	2023.11.14
No	Revisions	Date

Orientation	Seal
	a+Link PROJECT NO: 1953A

The Contractor shall check and verify all dimensions and report all errors and omissions to the IO-Owner's/MBS Designee (as applicable) for his/her written direction before proceeding with the Work.

A	Detail No
B	Sheet No where detailed



Colliers  
Project Leaders

**a+LINK**  
architecture inc.  
preserve + create + sustain  
P 519.649.0220 www.aLiNKarch.ca  
362 DUFFERIN AVENUE, LONDON ON N6B 1Z4



AMIS N B

Project  
UNIFIED FAMILY COURTHOUSE  
SECURITY UPGRADES

Location  
55 MAIN ST. WEST  
HAMILTON, ONTARIO  
IO Project No. 1102795 Site No. Building No.


Client  
COLLIERS PROJECT LEADERS

Drawing Title  
ENLARGED FLOOR PLAN DETAILS &  
LEGEND

Scale AS NOTED	Date 2025.02.13
Drawn by BA	Substantial Performance Date
Designed by	Drawing No A5.2 of 16
Approved by	CADD File NAME

FLOOR PENETRATION SCHEDULE					
PENETRATION NO.	FLOOR MATERIAL	HOLE DIA.	FASTNER TYPE	DEVICE MOUNTED	
GROUND FLOOR					
A1 - 3	MARBLE	½"	ANCHOR	TURNSTILES	
A4 - 6	MARBLE	½"	ANCHOR	TURNSTILES	

1  
A2.1 A5.1  
SCALE: 1:25  
MAIN ENTRANCE SECURITY BARRIER



1  
A2.1 A5.3  
SCALE: 1:25  
MAIN ENTRANCE SECURITY BARRIER - PENETRATION

5	ISSUED FOR 99% CLIENT REVIEW	2025.02.13
4	ISSUED FOR 99% CLIENT REVIEW	2024.12.09
3	ISSUED FOR 66% REV CLIENT REVIEW	2024.08.16
2	ISSUED FOR 66% CLIENT REVIEW	2024.03.13
1	ISSUED FOR 33% CLIENT REVIEW	2023.11.14
No	Revisions	Date

Orientation

Seal

a+Link PROJECT NO: 1953A

The Contractor shall check and verify all dimensions and report all errors and omissions to the IO-Owner's/MBS Designee (as applicable) for his/her written direction before proceeding with the Work.

A

B

A Detail No

B Sheet No where detailed



Colliers  
Project Leaders

**a+LiNK**  
architecture inc.  
preserve + create + sustain

P 519.649.0220 [www.aLiNKarch.ca](http://www.aLiNKarch.ca)  
362 DUFFERIN AVENUE, LONDON ON N6B 1Z4



AMIS N B

Project  
UNIFIED FAMILY COURTHOUSE  
SECURITY UPGRADES


Location  
55 MAIN ST. WEST  
HAMILTON, ONTARIO  
IO Project No. Site No. Building No.  
1102795

Client  
COLLIERS PROJECT LEADERS

Drawing Title  
PENETRATION PLAN, SCHEDULE &  
LEGEND

Scale AS NOTED	Date 2025.02.13
Drawn by BA	Substantial Performance Date
Designed by —	Drawing No A5.3 of 16
Approved by	CADD File NAME





1  
A2.4 | A5.4  
SCALE: 1:25  
SECOND FLOOR

5	ISSUED FOR 99% CLIENT REVIEW	2025.02.13
4	ISSUED FOR 99% CLIENT REVIEW	2024.12.09
3	ISSUED FOR 66% REV CLIENT REVIEW	2024.08.16
2	ISSUED FOR 66% CLIENT REVIEW	2024.03.13
1	ISSUED FOR 33% CLIENT REVIEW	2023.11.14
No	Revisions	Date

Orientation

Seal

a+Link PROJECT NO: 1953A

The Contractor shall check and verify all dimensions and report all errors and omissions to the IO-Owner's/MBS Designee (as applicable) for his/her written direction before proceeding with the Work.

A	Detail No
B	Sheet No where detailed



Colliers  
Project Leaders

**a+LiNK**  
architecture inc.  
preserve + create + sustain

P 519.649.0220      www.aLiNKarch.ca  
362 DUFFERIN AVENUE, LONDON ON N6B 1Z4



AMIS      N      B


Project  
UNIFIED FAMILY COURTHOUSE  
SECURITY UPGRADES

Location  
55 MAIN ST. WEST  
HAMILTON, ONTARIO  
IO Project No.      Site No.      Building No.  
1102795

Client  
COLLIERS PROJECT LEADERS

Drawing Title  
ENLARGED FLOOR PLAN DETAILS &  
LEGEND


Scale AS NOTED	Date 2025.02.13
Drawn by BA	Substantial Performance Date
Designed by —	Drawing No A5.4 of 16
Approved by	CADD File NAME



BF LAWYERS BYPASS - ELEVATION

8  
A5.2 | A8.1


SCALE: 1:25



SERT. GLAZING AT PUBLIC ENTRY - ELEVATION

4  
A5.2 | A8.1


SCALE: 1:25



HERITAGE STR. EXT. ONLY - ELEVATION

11  
A5.2 | A8.1


SCALE: 1:25



DOOR AT POLICE ZONE - ELEVATION

7  
A5.2 | A8.1


SCALE: 1:25



TURNSTILES & SERT. BARRIER UPON EXIT - ELEVATION

3  
A5.2 | A8.1


SCALE: 1:25



HERITAGE STR. EXT. ONLY - ELEVATION

10  
A5.2 | A8.1


SCALE: 1:25



SERT. BARRIER BEHIND POLICE ON - ELEVATION

6  
A5.2 | A8.1


SCALE: 1:25



HALF WALL AROUND SERT. EQUIP. - ELEVATION

2  
A5.2 | A8.1


SCALE: 1:25



SERT. GLAZING AT ENTRY MAG - ELE.

9  
A5.2 | A8.1


SCALE: 1:25



HALF DOORS & WALL SERT. EQUIP. - ELEVATION

5  
A5.2 | A8.1

SCALE: 1:25



SERT. HALF WALL - ELEVATION

1  
A5.2 | A8.1

SCALE: 1:25

5	ISSUED FOR 99% CLIENT REVIEW	2025.02.13
4	ISSUED FOR 99% CLIENT REVIEW	2024.12.09
3	ISSUED FOR 66% REV CLIENT REVIEW	2024.08.16
2	ISSUED FOR 66% CLIENT REVIEW	2024.03.13
1	ISSUED FOR 33% CLIENT REVIEW	2023.11.14

No	Revisions	Date

Orientation

Seal

a+Link PROJECT NO: 1953A

The Contractor shall check and verify all dimensions and report all errors and omissions to the IO-Owner's/MBS Designee (as applicable) for his/her written direction before proceeding with the Work.

A	Detail No
B	Sheet No where detailed



Colliers  
Project Leaders

**a+LiNK**  
architecture inc.  
preserve + create + sustain  
P 519.649.0220 www.aLiNKarch.ca  
362 DUFFERIN AVENUE, LONDON ON N6B 1Z4



AMIS N B

Project  
UNIFIED FAMILY COURTHOUSE  
SECURITY UPGRADES

Location  
55 MAIN ST. WEST  
HAMILTON, ONTARIO  
IO Project No Site No Building No  
1102795  
Client

Drawing Title  
INTERIOR ELEVATION

Scale AS NOTED	Date 2025.02.13
Drawn by BA	Substantial Performance Date
Designed by —	Drawing No A8.1 of 16
Approved by —	CADD File NAME



# APPENDIX E: Product Data





## CYLINDER SPEED GATE MT310-S

The **MT310-S speed gate** has a slender, cylindrical body with a horizontal arm or barrier that rotates in a vertical plane. It can work as a single(1pcs) or a pair(2pcs).

The MT310-S mechanism uses cutting edge technology to min the size but ensure the high performance. They are also equipped with famous brand servo motor,which is fast speed and wide lane.The lane width of a single can be set to 600-1000mm. The lane width of a pair can be set to 600-2000mm, which can be used for wheelchair, luggage or bicycle access.

MT310-S can be set to allow access in a bi-direction or single-directional based on client's requirement.

Cylinder pedestrian swing gates are space-efficient and suitable for locations with limited space as they don't require much room for installation. These turnstiles are deployed in a wide range of environments, from public transit stations and airports to corporate offices, stadiums, and high-security facilities. They help regulate pedestrian flow and enhance security.



40-50

PASSING SPEED



PASSAGE FOR DISABLE



BI-DIRECTION



110V-220V  
POWER SUPPLY




ANTI-TAILGATING



IP<sub>41</sub>  
PROTECTIVE LEVEL

# Technical Specifications

Dimension	φ168*1000mm (0.55*3.28*ft) (standard)
Material	SUS 304
Swing arm Material	Acrylic/Stainless steel
Passage Width (Single pcs)	600mm (1.97ft) -1000mm(3.28ft)
Passage Width of stainless steel arm (A pair)	600mm (1.97ft) -2000mm (6.56ft)
Passage Width of acrylic arm (A pair)	600mm (1.97ft) -1800mm (5.91ft)
Passage direction	Unidirectional/Bi-directional
Mechanism	Servo Motor 200W
Pass rate	40-50 persons/minute
Operating time	0.2 seconds
Power Supply	100V-240V 50/60Hz
Radar for automatic open	Unidirectional/Bi-directional
Open Signal	Passive Relay (Dry Contact)
Communication	RS485
MCBF	3,000,000 Cycles
Working Temperature	-35°C ~ 60°C
Working Environment	Indoor
Relative Humidity	95% Maximum



If you need a dimension drawing according to the site, please contact us.

## Feature

- EMERGENCY EXIT**  
 The function allows free passage in the event of an emergency or power outage, automatic reset when power is restored.
- WORKING DIRECTION**  
 Single directional or Bi-directional is optional.
- WORKING MODE**  
 Single pcs or a pair.
- AUTOMATIC RESET**  
 The swing arms will lock automatically within 5s (adjustable) if a person delay to access.
- SELF-CHECK**  
 With zero self-check function, convenient for user maintenance and use.
- FAST UNLOCK**  
 When there is a valid signal ,the gate will unlock within 0.2s (adjustable).
- ANTI-PASS BACK**  
 The gate will alarm if someone wants to entry in the reverse direction.
- ANTI-INTRUSION**  
 The gate is locked automatically until a invalid open signal is sent.
- ARM LED LIGHT**  
 LED on arms are optional function.
- LANE STATUS**  
 LED if the access is granted, the LED will be in green. In standby, the LED is blue. If denied access, the LED flash red.
- HIGH PERFORMANCE**  
 The whole system runs smoothly with low noise.

## Customization

- Dimension: Can be made according to the client's site.
- Optional use as a single (1pcs) or pair (2pcs).
- Material: 304 stainless steel to 316 stainless steel, or iron with powder coated (color can be customized).
- Swing arm material available in stainless steel or acrylic.
- Mounting base (for above floor wiring) and removable base (for temporary events) can be added.
- Cutouts can be customized to fit any reader. The cutouts can also be canceled.
- LOGO can be customized.
- Customized 3D drawings are available based on the site photos.
- OEM& ODM service is available.

## Access control system

*Our gates come with relay signals and RS485/RS232 interfaces. You can use your own access control system, or we can provide a complete access control system to you.*



Remote control



RFID card



QR code/ barcode



Counter



Face recognition



Fingerprint recognition



Coin/Card collection



Button

## We also offer customization services.



*Other frame colors available, RAL or RGB required.*



Black



Gray



Green




Blue



Red

*Cutouts can be customized to fit any reader. LOGO can be customized.*



*Various swing arms available*



*With mounting base*


**MAIRS**



## Emergency mode



Powered of equipment  
with Super Capacitor Backup



In case of a power outage, swing arms are unlocked  
and open automatically.

## Lane combination



One lane (Single one)



One lane (A pair)



Two lanes (Supports various combinations)



a+LiNK  
architecture inc.  
preserve + create + sustain





HERITAGE PERMIT REVIEW SUBCOMMITTEE  
Meeting Date: July 15, 2025

## City of Hamilton - Heritage Permit Application Note Sheet

**Address:** 122 McNab Street South, Hamilton (MacNab-Charles Heritage Conservation District, Part V)

**Permit Number:** HP2025-023

**Owner:** Gordon Robertson

**Applicant/Agent:** Same as above

### Description of proposed alterations:

- Restoration of the brick parapet on the south-west corner of the rear wing of the building, including:
  - Repointing with a 1-1-6 course cream line mortar with pigment to match; and,
  - Installing true pressed clay bricks (lbstock) to replace missing or damaged bricks, to match the existing bricks.

### Reasons for proposed alterations:

- Parapet is in poor condition, with brick that needs to be re-mortared or replaced.
- Work is required for the property to comply with an order issued under the City's Property Standards By-law.

### Documentation submitted with application:

- Heritage Permit application form
- Property Standards Order

### Draft Conditions for Consideration:

- ☐ That the proposed masonry repairs be conducted in accordance with the City's Masonry Restoration Guidelines and that the mortar repointing specifications be submitted, to the satisfaction and approval of the Director of Planning and Chief Planner, prior to commencement of any alterations;
- ☐ That any minor changes to the plans and elevations following approval shall be submitted, to the satisfaction and approval of the Director of Planning and Chief Planner;

## HERITAGE PERMIT REVIEW SUBCOMMITTEE

Meeting Date: July 15, 2025

Planner, prior to submission as part of any application for a Building Permit and / or the commencement of any alterations; and

- ☐ That implementation / installation of the alteration(s), in accordance with this approval, shall be completed no later than December 31, 2025. If the alteration(s) are not completed by December 31, 2025, then this approval expires as of that date and no alterations shall be undertaken without a new approval issued by the City of Hamilton.

## **Relevant MacNab-Charles HCD Policies (By-law No. 90-144)**

---

### **2.2.2 Architectural Guidelines for Restoration**

Policies for the restoration of buildings, located within the Heritage Conservation District, apply to buildings in Category A and B.

The following policies have been selected for their relevance to the restoration of the MacNab-Charles Block (based on the Secretary of the Interior's "Standards for Rehabilitation").

#### **I. Masonry: brick, stone, stucco and mortar**

##### **Recommended**

- Retaining original masonry and mortar, whenever possible, without the application of any surface treatment.
- Repointing only those mortar joints where there is evidence of moisture problems, or when sufficient mortar is missing to allow water to stand in the mortar joint.
- Duplicating old mortar in strength, composition, colour, and texture.
- Duplicating old mortar in joint size, method of application, and joint profile.
- Cleaning masonry only when necessary, to halt deterioration or to remove graffiti and stains, and always with the gentlest method possible, such as low pressure water, and soft, natural, bristle brushes.
- Repairing or replacing, where necessary, deteriorated material with new material that duplicates the old as closely as possible.
- Replacing missing significant architectural features, such as cornices, brackets, - etc.
- Retaining the original or early colour and texture of masonry surfaces. Brick or stone surfaces may have been painted or whitewashed for practical and aesthetic reasons.
- Repairing stucco with a stucco mixture that duplicated the original as closely as possible, in appearance and texture.

##### **Not Recommended**

- Applying waterproof or water repellant coatings, or surface consolidation treatments, unless required to solve a specific technical problem that has been studied and identified. Coatings are frequently unnecessary, expensive and can accelerate deterioration of the masonry.
- Repointing mortar joints that do not need repointing. Using electric saws and hammers to remove mortar can seriously damage the adjacent brick.

## HERITAGE PERMIT REVIEW SUBCOMMITTEE

Meeting Date: July 15, 2025

- Repointing with mortar of high Portland cement content can often create a bond that is stronger than the building material. This can cause deterioration as a result of the differing co-efficient of expansion, and the differing porosity of the material and the mortar.
- Repointing with mortar joints of a differing size or joint profile, texture or colour.
- Sandblasting, including dry and wet grit and other abrasives, brick or stone surfaces; this method of cleaning erodes the surface of the material and accelerates deterioration. Using chemical cleaning products that would have an adverse chemical reaction with the masonry materials, i.e., acid on limestone or marble.
- Applying new material which is inappropriate, or was unavailable when the building was constructed, such as artificial brick siding; artificial cast stone, or brick veneer.
- Removing architectural features such as cornices; brackets; railings; shutters; window architraves; and doorway pediments.
- Removing paint from masonry surfaces indiscriminately. This may subject the building to damage and change its appearance.

## Description of Heritage Attributes (Heritage Conservation Easement Agreement)

---

The Heritage Attributes at 122 MacNab Street South, City of Hamilton, protected by this heritage conservation easement agreement include, but are not restricted to, the following:

Key elements that express the design/physical value of 122 MacNab Street South, including:

- Elements related to the construction of the two-storey stone terrace as a representative example of the vernacular-Classical Revival architectural style, including:
  - The east and north elevations of the house, including the construction-coursed ashlar limestone in the front (east) facade, and the rubblestone in the side (north) facade;
  - The roofline, including:
    - The projecting eaves and parapets;
  - The window and door openings, including any remaining historic wood windows on the east and north elevations, and the stone voussoirs and sills;
  - The front door and transom; and,
  - The stone foundation.



HERITAGE PERMIT REVIEW SUBCOMMITTEE  
Meeting Date: July 15, 2025

## Photographs

---




Figure 1: Front view of 122 McNab Street South from Google Map Street View (June 2024).

HERITAGE PERMIT REVIEW SUBCOMMITTEE  
Meeting Date: July 15, 2025




Figure 2: Photo of rear southwest parapet requiring repair



HERITAGE PERMIT REVIEW SUBCOMMITTEE  
Meeting Date: July 15, 2025

## City of Hamilton - Heritage Permit Application Note Sheet

**Address:** 47 James Street South, Hamilton (Landed Banking and Loan Company Building, Part IV)

**Permit Number:** HP2025-025

---

**Owner:** Michelle Blanchard, Wilson Blanchard

**Applicant/Agent:** Sarah Francisca, John G. Cooke & Associates Ltd.

---

### Description of proposed alterations:

- Structural repairs of the existing brick parapet walls supporting the terra cotta parapet and balustrade at the roof level, including:
    - Repointing of brick at interior face of parapet, below architectural terra cotta;
    - Rebuilding of brick and replacement with compatible new brick, as required; and,
    - Removal and reinstatement of two architectural terra cotta units at interior face of parapet.
- 

### Reasons for proposed alterations:

- Existing brick parapet walls are deteriorating and in poor condition.
  - Removal and replacement of the two architectural terra cotta units is required for investigation of underlying conditions.
- 

### Documentation submitted with application:

- Heritage Permit application form
- Drawings and Specifications from John G. Cooke & Associates Ltd., Consulting Engineers (Attached as **Appendix "A"**)



HERITAGE PERMIT REVIEW SUBCOMMITTEE  
Meeting Date: July 15, 2025

---

**Draft Conditions for Consideration:**

- ☐ That the proposed masonry repairs be conducted in accordance with the City's Masonry Restoration Guidelines, to the satisfaction and approval of the Director of Planning and Chief Planner, prior to commencement of any alterations;
- ☐ That any minor changes to the plans and elevations following approval shall be submitted, to the satisfaction and approval of the Director of Planning and Chief Planner, prior to submission as part of any application for a Building Permit and / or the commencement of any alterations; and
- ☐ That implementation / installation of the alteration(s), in accordance with this approval, shall be completed no later than July 31, 2027. If the alteration(s) are not completed by July 31, 2027, then this approval expires as of that date and no alterations shall be undertaken without a new approval issued by the City of Hamilton.

HERITAGE PERMIT REVIEW SUBCOMMITTEE  
Meeting Date: July 15, 2025

### **Excerpt from Reasons for Designation (By-law No. 86-271)**

---

Of importance to the preservation of 47 James Street South is the retention of the original features on the west and south facades, including but not limited to the Indiana limestone columns and pilasters, the wall panels, fenestration, doorways, entablature and balustrade.

HERITAGE PERMIT REVIEW SUBCOMMITTEE  
Meeting Date: July 15, 2025

## Photographs

---



**Figure 1:** Front view of Landed Banking and Loan Company Building off James Street South from Google Maps (June 2024).



HERITAGE PERMIT REVIEW SUBCOMMITTEE  
Meeting Date: July 15, 2025

## Drawings

---

Please see drawings attached as **Appendix “A”** to this Note Sheet.



A. GENERAL NOTES

1. GENERAL INFORMATION

- 1.1. THE INFORMATION PRESENTED ON THESE DRAWINGS HAVE BEEN DESIGNED IN ACCORDANCE WITH THE ONTARIO BUILDING CODE 2024. CONSTRUCTION IS TO BE PERFORMED IN ACCORDANCE WITH THIS AND ALL OTHER APPLICABLE CODES AND STANDARDS NOTED HERIN. REFER TO SPECIFICATIONS FOR ALL OTHER APPLICABLE STANDARDS.
- 1.2. THE MATERIALS LISTED HEREIN APPLY TO THIS PROJECT, UNLESS NOTED OTHERWISE OR ON SPECIFICATIONS.
- 1.3. THESE DRAWINGS ARE FOR THE USE OF THE CLIENT ONLY. THE CONSULTANT DOES NOT GUARANTEE THAT THE DRAWINGS ARE ERROR-FREE, COMPLETE, OR FIT FOR ANY OTHER PURPOSE. THE INFORMATION SHOWN ON THE DRAWINGS STRICTLY APPLY TO THIS PROJECT ONLY. DECISIONS OR ACTIONS MADE BY THIRD PARTIES BASED ON THESE DRAWINGS IS THE SOLE RESPONSIBILITY OF SUCH PARTIES.
- 1.4. THESE DRAWINGS SHOW THE COMPLETED STRUCTURE. THE CONTRACTOR SHALL HAVE THE SOLE RESPONSIBILITY FOR THE DESIGN, ERECTION, OPERATION, MAINTENANCE, AND REMOVAL OF TEMPORARY SUPPORTS, STRUCTURES, AND FACILITIES, AND THE DESIGN AND EXECUTION OF CONSTRUCTION METHODS REQUIRED IN THEIR USE.
- 1.5. THE USE OF THESE DRAWINGS SHALL BE STRICTLY LIMITED TO THE INSTRUCTIONS IN THE REVISION BLOCK. BUILDING FROM THESE DRAWINGS SHALL PROCEED ONLY WHEN "ISSUED FOR CONSTRUCTION".
- 1.6. CONSTRUCTION TO BE IN CONFORMANCE WITH DETAILS IDENTIFIED AS BEING "TYPICAL", UNLESS NOTED OTHERWISE.

2. SITE CONDITIONS

- 2.1. THE SCOPE OF THE WORK DEPENDS ON THE SITE CONDITIONS. NOTIFY THE CONSULTANT WHERE ON-SITE CONDITIONS MAY REQUIRE MODIFICATIONS TO THE CONTRACT DOCUMENTS.
- 2.2. PROTECT ALL ADJACENT BUILDING MATERIALS INCLUDING WINDOWS, DOORS, FIXTURES, SIGNAGE, PLAQUES, LANDSCAPING AND SODDING IN AND ADJACENT TO THE WORK FOR THE DURATION OF THE WORK. MAKE GOOD AND RESTORE ALL DAMAGED AREAS TO MATCH EXISTING.
- 2.3. NOTIFY CONSULTANT AND OWNER OF ANY EXISTING CONDITIONS OR MATERIALS THAT MAY BECOME DAMAGED OR DISTURBED AS A RESULT OF THE WORK.
- 2.4. ALL FINAL COLOURS TO BE CONFIRMED BY OWNER PRIOR TO ORDERING MATERIAL.

3. DIMENSIONS

- 3.1. DO NOT SCALE DRAWINGS. CHECK ALL DIMENSIONS ON THE DRAWINGS WITH THE SITE CONDITIONS. REPORT ANY INCONSISTENCIES BEFORE PROCEEDING WITH THE WORK.
- 3.2. ALL DIMENSIONS ARE IN MILLIMETERS, UNLESS OTHERWISE NOTED.
- 3.3. BEFORE SUBMITTING BID FOR THE WORK, THE CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS, ELEVATIONS AND LOCATION OF EXISTING STRUCTURES.

4. FIELD REVIEW

- 4.1. THE CONSULTANT WILL CONDUCT PERIODIC INSPECTIONS AND PROVIDE CONSTRUCTION REVIEW REPORTS (CRR), OUTLINING PROGRESS OF WORK, AND STATING WHETHER OR NOT WORK CONFORMS TO THE CONTRACT DOCUMENTS.
- 4.2. CRR'S, WILL OUTLINE ANY DEFICIENCIES FOUND.
- 4.3. MATERIALS AND WORKMANSHIP NOT CONFORMING TO THE SPECIFICATIONS SHALL BE REJECTED.
- 4.4. NOTIFY CONSULTANT FOR REVIEW OF ALL RAKED OUT OR BACKPOINTED MORTAR JOINTS PRIOR TO PLACEMENT OF NEW MORTAR. CONSULTANT WILL REVIEW AND APPROVE FOR PLACEMENT OF MORTAR. PLACEMENT OF MORTAR PRIOR TO RECEIPT OF CONSULTANT ACCEPTANCE WILL BE CAUSE FOR REJECTION OF THE AFFECTED PART OF THE WORK.

5. MASONRY

- 5.1. DO NOT USE MASONRY CEMENT. USE PORTLAND CEMENT AND LIME ONLY.
- 5.2. INCLUDE FOR THE REMOVAL OF CAULKING, METAL NAILS OR PINS THAT MAY BE PRESENT IN THE JOINTS TO BE RAKED OUT.
- 5.3. COMPLETE A MIN. 300mm x 300mm MOCK-UP EACH OF:
- 5.3.1. RAKING OUT AND JOINT PREPARATION
- 5.3.2. BACKPOINTING
- 5.3.3. FINISHPOINTING, INCLUDING MORTAR COLOUR
- 5.3.4. BRICK REPLACEMENT / REBUILD
- 5.4. MORTAR COLOUR TO BE APPROVED BY CONSULTANT AND OWNER PRIOR TO PLACEMENT BEYOND MOCK-UP AREA.
- 5.5. ALL MORTAR JOINTS TO BE INSPECTED AND APPROVED BY CONSULTANT PRIOR TO POINTING. ANY MORTAR PLACED INTO JOINTS PRIOR TO RECEIPT OF CONSULTANT APPROVAL IS TO BE REMOVED AND REINSTALLED AT THE CONTRACTOR'S OWN EXPENSE.
- 5.6. REFER TO TYPICAL DETAILS FOR RAKING OUT AND REPOINTING OF MORTAR JOINTS.

6. ANCHORAGE

- 6.1. INSTALLATION OF ALL POST-INSTALLED ANCHORS TO BE IN CONFORMANCE WITH MANUFACTURER'S DIRECTIONS, INCLUDING BUT NOT LIMITED TO: DRILL BIT SIZE AND TYPE, HOLE CLEANING, TEMPERATURE, CURING, AND TORQUE.

B. MATERIAL AND DESIGN DATA

UNLESS NOTED OTHERWISE ON DRAWINGS OR ON SPECIFICATIONS, THE MATERIALS LISTED BELOW APPLY TO THIS PROJECT AND THE DESIGN AND CONSTRUCTION SHALL COMPLY WITH THE FOLLOWING CODES AND STANDARDS. ALL STANDARDS TO LATEST EDITION, UNLESS NOTED.


REFER TO SPECIFICATIONS FOR ALL OTHER APPLICABLE STANDARDS.

1. MASONRY DESIGN AND CONSTRUCTION: CSA S304-14 (R2019) & CAN/CSA-A371-14 (R2024)

MASONRY ELEMENT TYPE	DESIGN DATA	STANDARD
A REPLACEMENT BRICK:	'SOFT' BRICK, COLOUR TO MATCH EXISTING COMPRESSIVE STRENGTH: 20 TO 35MPa 24-HOUR COLD WATER ABSORPTION: 12-18% ACCEPTABLE PRODUCT: IBSTOCK BRICK, WIENERBERGER BRICK, OR WATSONTOWN BRICK. PROVIDE SAMPLE TO CONFIRM COLOUR PRIOR TO ORDERING. -ALTERNATES ARE ACCEPTABLE TO THE APPROVAL OF CONSULTANT.	CSA-A82:14 (R2023)
B MORTAR:	TYPE O ACCEPTABLE PRODUCT: KING MASONCARE 300 OR KING MASONMIX ALTERNATES ARE ACCEPTABLE TO THE APPROVAL OF CONSULTANT AND OWNER.	CAN/CSA-A179-14 (R2024)
C CONNECTORS FOR MASONRY:	STAINLESS STEEL (TYPE 304 OR 316)	CSA A370:14 (R2023)

C. CODES AND STANDARDS

1. CONFORM TO THE REQUIREMENTS OF THE ONTARIO BUILDING CODE 2024 AND THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS (LATEST EDITION).
2. MASONRY DESIGN AND CONSTRUCTION: CSA S304-14 (R2019) AND CAN/CSA-A371-14 (R2024), RESPECTIVELY.



DRAWING LIST


- S0.01 GENERAL NOTES AND SITE PLAN
- S1.01 EXISTING ROOF PLAN
- S2.01 PARAPET WALL ELEVATIONS
- S3.01 TYPICAL DETAILS

JOHN G. COOKE & ASSOCIATES LTD. CONSULTING ENGINEERS

www.jgcooke.com

OTTAWA, ON 17 FITZGERALD RD., SUITE 200 K2H 9G1 (613) 226-8718

HAMILTON, ON 20 HUGHSON ST. S. SUITE 906 L8N 2A1 (289) 288-3638



SEAL:

LICENSED PROFESSIONAL ENGINEER

J. K. DEE

100162005

JUN-23-2025

PROVINCE OF ONTARIO

issued or revised		
02	ISSUED FOR BUILDING PERMIT	2025-06-23
01	ISSUED FOR PRICING	2025-06-23
no.	description	date

PROJECT:

BRICK PARAPET REPAIRS

47 JAMES STREET S, HAMILTON, ONTARIO

DRAWING:

GENERAL NOTES AND SITE PLAN

DESIGNED BY: SF / JD


DRAWN BY: CP

SCALE: AS SHOWN DATE: 2025-05-08

PROJECT No. 25115

DRAWING No.

R0.01



JOHN G.  
**COOKE**  
& ASSOCIATES LTD.  
CONSULTING ENGINEERS  
www.jgcooke.com

OTTAWA, ON  
17 FITZGERALD RD., SUITE 200  
K2H 9G1  
(613) 226-8718

HAMILTON, ON  
20 HUGHSON ST. S., SUITE 906  
L8N 2A1  
(289) 288-3638

KEY PLAN  
SCALE NTS

SEAL:

issued or revised

02	ISSUED FOR BUILDING PERMIT	2025-06-23
01	ISSUED FOR PRICING	2025-06-23
no.	description	date

PROJECT:

**BRICK  
PARAPET REPAIRS**  
47 JAMES STREET S,  
HAMILTON, ONTARIO

DRAWING:

**EXISTING ROOF PLAN**

DESIGNED BY: \_\_\_\_\_ SF / JD

DRAWN BY: \_\_\_\_\_ CP

SCALE: \_\_\_\_\_ DATE: \_\_\_\_\_


AS SHOWN 2025-05-08

PROJECT No. 25115


DRAWING No. \_\_\_\_\_

**R1.01**







1 INTERIOR ELEVATION OF WEST PARAPET  
R2.01 1:50



2 INTERIOR ELEVATION OF EAST PARAPET  
R2.01 1:50



3 INTERIOR ELEVATIONS OF SOUTH PARAPET  
R2.01 1:50



4 INTERIOR ELEVATIONS OF NORTH PARAPET  
R2.01 1:50

DRAWING NOTES:

- FOR FULL EXTENT OF INTERIOR FACE OF PARAPET WALL BELOW TERRA COTTA UNITS:
  - REMOVE EXISTING METAL FLASHING.
  - REMOVE EXISTING ROOFING MEMBRANE FLASHING.
  - REMOVE EXISTING PARGING TO EXPOSE BRICK MASONRY.
  - REPOINT 100% OF EXPOSED MORTAR JOINTS IN BRICK MASONRY, FROM T/O SLAB TO U/S OF TERRA COTTA.
  - REBUILD BRICK MASONRY AT UNIT RATES, AT UNIT RATES AND IN ACCORDANCE WITH QUANTITY TABLE BELOW, AS DIRECTED ON SITE BY CONSULTANT.
  - REPLACE FAILED EXISTING BRICK WITH NEW BRICK, AT UNIT RATES AND IN ACCORDANCE WITH QUANTITY TABLE BELOW, AS DIRECTED ON SITE BY CONSULTANT.
  - COORDINATE/SEQUENCE WORK WITH ROOFING WORK (BY OTHERS).
- EX. PIER EXTENSIONS CLAD WITH METAL CAP AND COUNTER FLASHING. REMOVE FLASHING AND ROOFING, AND REPAIR UNDERLYING BRICK MASONRY (ASSUMED) AS FOR ITEM 1.
- EX. ROOFING AND FLASHING TO BE REPLACED WITH NEW ROOF ASSEMBLY (BY OTHERS).
- EX. TERRA COTTA PARAPET UNITS (AS SHADED) TO REMAIN.
- EX. METAL FLASHING TO REMAIN.
- REMOVE BULGING SECTION OF EX. METAL SIDING. ALLOW CONSULTANT TO INSPECT EXPOSED UNDERLYING BRICK MASONRY. REINSTATE SIDING INTO S-LOCK JOINTS ALONG ADJACENT PANELS. FASTEN USING STAINLESS STEEL FASTENERS WITH NEOPRENE WASHERS, IF REQ.
- EXISTING EXPOSED BRICK IN FAIR CONDITION AT INSIDE FACE OF PARAPET WALL, TO REMAIN. CONSULTANT TO REVIEW CONDITION OF BRICK MASONRY EXPOSED UPON REMOVAL OF EXISTING FLASHING AND ROOFING MEMBRANE DURING ROOFING WORK (BY OTHERS).
- PROVIDE OPTIONAL PRICE TO COMPLETE INVESTIGATORY REMOVALS, AS FOLLOWS:
  - CAREFULLY REMOVE AND SALVAGE EXISTING TERRA COTTA UNITS INDICATED.
  - ALLOW FOR CONSULTANT TO REVIEW EXPOSED CONDITIONS.
  - REINSTATE SALVAGED TERRA COTTA UNIT, USING SAME MORTAR AS INDICATED FOR BRICK, ELSEWHERE.
  - FOR PRICING ASSUME THAT REINSTATING UNITS WILL REQUIRE PLACEMENT OF 4 NEW BENT 304 STAINLESS STEEL (SS) ANCHORS (3 mm TK. PLATE, 75 WD., UP TO 300 LG.) C/W 10 SS THREADED ROD DOWELS AND SS ANCHORAGE TO BACKUP MASONRY. CONSULTANT WILL PROVIDE DIRECTION UPON REMOVALS.

MASONRY REPAIR QUANTITIES:


REPAIR TYPE	UNIT	QUANTITY
<b>DISMANTLE AND REBUILD BRICK MASONRY:</b> REMOVE, SALVAGE AND RESET EXISTING BRICK AS DIRECTED BY CONSULTANT AND IN ACCORDANCE WITH TYPICAL DETAILS. KEY REBUILD AREA TO BACKUP WITH NEW HEADER BRICKS, TO MATCH EXISTING BOND PATTERN. ASSUME HELICAL ANCHORS TO BE INSTALLED AT 400 O.C. EACH WAY. QUANTITIES SHALL BE RECORDED ON A PER WYTHE BASIS WHERE REBUILDING OF BACKUP WYTHES IS REQUIRED. (E.G. IF 1.0m² OF OUTER AND 0.5m² OF INNER WYTHE REBUILDING IS REQUIRED. THIS WOULD BE RECORDED AS 1.5m²)	m²	25
<b>REPLACE WITH NEW BRICK:</b> SUPPLY NEW BRICK TO REPLACE BRICKS REMOVED DURING REBUILDING WHICH HAVE BEEN DEEMED UNSUITABLE FOR REUSE BY CONSULTANT. COST TO INCLUDE MATERIAL SUPPLY ONLY, CREDITING UNNECESSARY SALVAGING WORK, INSTALLATION COSTS ARE INCLUDED IN 'RB' TYPE REPAIR.	m²	20

PROVIDE PRICING AT UNIT RATES FOR QUANTITIES INDICATED IN TABLE ABOVE.

JOHN G.  
**COOKIE**  
& ASSOCIATES LTD.  
CONSULTING ENGINEERS  
www.jgcookie.com

OTTAWA, ON  
17 FITZGERALD RD., SUITE 200  
K2H 9G1  
(613) 226-8718

HAMILTON, ON  
20 HUGHSON ST. S. SUITE 906  
L8N 2A1  
(289) 288-3638



SEAL:

LICENSED PROFESSIONAL ENGINEER  
J. K. DEE  
100162005  
JUN-23-2025  
PROVINCE OF ONTARIO

no.	description	date
02	ISSUED FOR BUILDING PERMIT	2025-06-23
01	ISSUED FOR PRICING	2025-06-23

PROJECT:

BRICK  
PARAPET REPAIRS  
47 JAMES STREET S.  
HAMILTON, ONTARIO


DRAWING:

PARAPET WALL  
ELEVATIONS

DESIGNED BY: SF / JD  
DRAWN BY: CP  
SCALE: AS SHOWN DATE: 2025-05-08  
PROJECT No. 25115  
DRAWING No.

R2.01





RAKING OUT PROCEDURE:

1. RAKE OUT EXISTING MORTAR SQUARE TO BRICK.
2. REMOVE ALL OVERPOINTING FROM BRICK FACE.
3. CLEAN OUT JOINT USING COMPRESSED AIR, OR WASH OUT JOINTS USING PRESSURIZED WATER, PRIOR TO REPOINTING.
4. REMOVE ALL RESIDUE FROM BRICK FACE TO ALLOW NEW MORTAR TO BOND TO BRICK.


NOTES:

- DO NOT CHIP OR OTHERWISE DAMAGE EDGE OF BRICK DURING REMOVALS.
- GRINDERS OR SAW BLADES MUST NOT TOUCH BRICK FACE. CUT CENTRE OF JOINT CAREFULLY, WITHOUT MARKING BRICK. REMOVE REMAINDER OF MORTAR USING HAND TOOLS. MECHANICAL TOOLS ONLY TO BE USED WHEN APPROVED TO MAKE RELIEF CUTS IN THE CENTRE OF JOINTS.
- ALL CRACKED MORTAR, MORTAR DEBONDED FROM BRICK, OR DETERIORATED MORTAR, MUST BE REMOVED FROM JOINT PRIOR TO REPOINTING.
- INTENT IS TO REMOVE ALL PORTLAND CEMENT BASED MORTARS FROM JOINTS.
- REFER TO SCOPE OF WORK, DEFINED ELSEWHERE, FOR PROJECT REQUIREMENTS.
- REMOVE ALL CAULKING, WHERE PRESENT IN JOINTS.
- NOTIFY CONSULTANT WHERE BRICK BECOMES LOOSE.
- WHERE FULL DEPTH REMOVALS IN HORIZONTAL JOINTS ARE NECESSARY, EXERCISE CAUTION SO AS NOT TO DESTABILIZE THE WALL. IN THIS CASE, REMOVE MORTAR IN ONLY SMALL PORTIONS OF THE WALL AND REPOINT EXCEPT FOR FINAL LAYER BEFORE PROCEEDING WITH RAKING OUT.

FOR PRICING, ASSUME THE FOLLOWING:

1. AVERAGE DEPTH OF BRICK: 100mm.
2. CEMENTITIOUS PARGING MUST BE REMOVED FROM THE FACE OF THE WALL PRIOR TO REPOINTING. 50% OF THIS PARGING IS DELAMINATED FROM THE BRICK.
3. 60% OF REMOVALS FOR VERTICAL JOINTS ARE IN THE ORDER OF 30 TO 40mm DEEP AND THE REMAINDER ARE FULL DEPTH REMOVALS.
4. 40% OF REMOVALS FOR HORIZONTAL JOINTS ARE IN THE ORDER OF 30 TO 40mm DEEP AND THE REMAINDER ARE FULL DEPTH REMOVALS.


1 TYPICAL RAKING OUT DETAIL  
R3.01 NTS



NOTES:

- BACKPOINTING: REQUEST INSPECTION TO REVIEW PRIOR TO BACKPOINTING. REQUEST INSPECTION FOR REVIEW OF COMPLETED BACKPOINTING BEFORE PROCEEDING TO MASONRY REPAIRS AND FINISHPOINTING.

2 TYPICAL REPOINTING DETAIL  
R3.01 NTS




MATERIALS:

1. RETROFIT ANCHOR TYPE: STAINLESS STEEL HELICAL WALL TIE.
2. ANCHOR DIAMETER: 8mmØ
3. ANCHOR LENGTH: 195mm
4. RECOMMENDED PRODUCT IS SPIRAL-LOK BY BLOK-LOK. SUBMIT DATA SHEETS FOR REVIEW. DRILL TYPE: BECAUSE THE BACK-UP MATERIAL IS BRICK, A SPECIALIZED DRILL IS REQUIRED, WHICH HAS A REDUCED POWER HAMMER SETTING.
- 5.1. APPROVED DRILLS:
  - HILTI TE 2-S DRILL, WITH A 30% HAMMER ACTION SETTING
  - HIGH SPEED ROTARY PERCUSSION DRILL, 3-JAW CHUCK TYPE.


INSTALLATION INSTRUCTIONS:

1. FOLLOW MANUFACTURER'S INSTRUCTIONS, AND NOTE THE FOLLOWING.
2. INSTALLATION TYPE: BRICK TO BRICK (ENTRY THROUGH MORTAR JOINT)
  - 2.1. DRILL 5mm PILOT HOLE INTO MORTAR JOINT IN BRICK BACK-UP, MIN. 75mm EMBEDMENT.
  - 2.2. DRILL TYPE FOR PILOT HOLE TO BE AS PER NOTE 5.1
  - 2.3. HOLE LOCATION SHALL BE IN BED JOINT, AVOIDING AS BEST AS POSSIBLE THE CORES OF THE BRICK, AND NOT IN THE 'T' JOINT.
  - 2.4. INSTALL 8mm SPIRA-LOK ANCHOR, DRIVEN INTO POSITION USING THE BLOK-LOK DRY SET INSTALLATION TOOL. MOUNTED ON AN ELECTRIC SDS HAMMER DRILL. ANCHOR TO BE INSET INTO MORTAR JOINT BY 10mm.
- 2.5. EMBED ANCHORS INTO BED JOINTS OF NEW BRICK TO BE REBUILT.

3 TYPICAL RETROFIT ANCHOR DETAIL  
R3.01 NTS




4 TYPICAL BRICK DISMANTLE AND REBUILD  
R3.01 NTS



NOTES:

1. ALLOW FOR REPOINTING BEHIND ALL EXISTING FLASHING, ONCE EXISTING FLASHING IS REMOVED. ASSUMED RAKE OUR AND REPOINTING DEPTH IS 100mm. SEE DETAILS 1 AND 2 ON R3.01.
2. SEE ROOF REPLACEMENT DRAWINGS (BY OTHERS) FOR BALANCE OF ROOFING AND FLASHING WORK.

5 TYPICAL REGLET DETAIL CUT INTO STONE MASONRY  
R3.01 NTS



NOTES:


1. ALLOW FOR REPOINTING BEHIND ALL EXISTING FLASHING, ONCE EXISTING FLASHING IS REMOVED. ASSUMED RAKE OUR AND REPOINTING DEPTH IS 100mm. SEE DETAILS 1 AND 2 ON R3.01.
2. SEE ROOF REPLACEMENT DRAWINGS (BY OTHERS) FOR BALANCE OF ROOFING AND FLASHING WORK.

6 TYPICAL REGLET DETAIL CUT INTO MORTAR JOINT  
R3.01 NTS

JOHN G.  
**COOKIE**  
& ASSOCIATES LTD.  
CONSULTING ENGINEERS  
www.jgcookie.com

OTTAWA, ON  
17 FITZGERALD RD., SUITE 200  
K2H 9G1  
(613) 226-8718

HAMILTON, ON  
20 HUGHSON ST. S. SUITE 906  
L8N 2A1  
(289) 288-3638



SEAL:



issued or revised

no.	description	date
02	ISSUED FOR BUILDING PERMIT	2025-06-23
01	ISSUED FOR PRICING	2025-06-23

PROJECT:

BRICK  
PARAPET REPAIRS  
47 JAMES STREET S.  
HAMILTON, ONTARIO

DRAWING:

TYPICAL DETAILS

DESIGNED BY: SF / JD

DRAWN BY: CP

SCALE: AS SHOWN DATE: 2025-05-08

PROJECT No. 25115

DRAWING No.

R3.01